ACE MANUFACTURING SYSTEMS LTD

AMS
In Pursuit of Excellence

INDEX - MACHINE HISTORY

MACHINE NUMBER : M 11- 805

SL NO	DESCRIPTION	FORMAT NUMBER	ENCLOSED
1	MACHINE DISPATCH CLEARANCE	F-QA-FA -16	✓
2	PACKING LIST / DISPATCH DETAILS	F-TSG-18 & F-PAC-01	✓
3	MINUTES OF MEETING	F-TSG-17	NA
4	WORK ORDER	F-TSG-15	✓
5	MACHINE SEQUENCE RUNNING REPORT	F-QA-FA-12	✓
6	SPINDLE STABILISATION REPORT	F-QA-FA-11	✓
7	MACHINE HEALTH CHECK POINTS	F-QA-FA-09	✓
8	CHECK LIST - MECHANICAL	F-QA-FA-07	✓
9	MACHINE HISTORY - MECHANICAL	F-QA-FA-10	✓
10	CHECK LIST - ELECTRICAL	F-QA-FA-08	✓
11	MACHINE HISTORY - ELECTRICAL	F-QA-FA-14	✓
12	FINAL ASSEMBLY REPORT - MECHANICAL	F-QA-FA-05/15	✓
13	GEOMETRICAL TEST REPORT	DS-DSN-PROD-TC 01~ 06	✓
14	PRACTICAL TEST REPORT	F-TSG -34	✓
15	SPINDLE BALANCING REPORT	F-QA-FA-04	✓
16	SPINDLE ASSEMBLY	F-QA-IPR-SPL- 01	✓
17	HYDRAULIC ASSEMBLY REPORT (OPTIONAL)	F-QA-IPR-HYD-01	✓
18	BALL BAR REPORT	F-QA-FA-02	✓
19	AXIS CALIBRATION REPORT	F-QA-FA-01	✓
20	GEAR BOX / ATC ASSEMBLY	F-QA-IPR-GBA- 01 / SUPPLIER REPORT	✓
21	BALL SCREW ASSEMBLY	F-QA-IPR-BSA- 01	✓
22	BASE BUILDING	F-QA-IPR-BBA- 01/ 02	✓

Date : 28/02/12 V. Gopal CHECKED BY APPROVED BY

ACE MANUFACTURING SYSTEMS LTD

MACHINE DISPATCH CLEARANCE

AMS
In Pursuit of Excellence

M/c No.: M11 - 805	CUSTOMER : M/s, SHAKTI COMP
MODEL : MCV-400	DATE : 03 - 05 - 2012

DEVIATION DETAILS

ASSEMBLY IN CHARGE | QUALITY IN CHARGE | AUTHORIZED SIGNATURE

CORRECTIVE ACTION (BY CSG)

RESPONSIBLE PERSON : SIGNATURE OF CSG HOD

Note : Customer Support Group (CSG) will confirm the closure of deviation and Return to QA.

400

ACE MANUFACTURING SYSTEMS LTD.

MACHINE DISPATCH CHECK POINTS

AMS — In Pursuit of Excellence

CUSTOMER'S NAME: Sakthi Auto component Ltd. Erode.

M/C No.: MH-805 MCV-400 DATE: 05-05-12 7-5-12 9.45PM

S.No	DESCRIPTION	YES/ NO/NA	S.No.	DESCRIPTION	YES/ NO/NA
1	Packing list available	Yes	21	Chip Trolley cleaned	Yes
2	Hydraulic / Pneumatic Counter Balance Cylinder removed	NA	22	Standard Spares & m/c manual available	Yes
3	Z- Motor Cover Removed & Packed	NO	23	Coolant tank assly. packed	NA
4	Side door handles removed & Packed	NO	24	Index Table Cover packed properly	NA
5	Base guard removed & Packed	Yes	25	Oil skimmer bin cleaned	Yes
6	Coolant Gun tied properly	Yes	26	Voltage Stabilizer packed	NA
7	Air gun tied properly	NA	27	Machine Platform cleaned	NA
8	Leveling Screws, Nuts removed & Packed	Yes	28	Wanner Pump & cover cleaned & put back	NA
9	Leveling blocks 100/180/220/300 Ht. Qty: - 4/6/7/8/11/20	Yes	29	Customer components packed properly	NA
10	Automatic Tool Changer	Yes	30	Index Table packed properly	NA
11	APC Assembly packed Properly	NA	31	Chiller unit cleaned	NA
12	Pallet removed & Packed	NA	32	Rotary Table packed properly	NA
13	APC leveling screws - 1set	NA	33	Toolings packed properly	NA
14	Power pack stand	NA	34	Tail Stock packed properly	NA
15	Lub Tank oil drained - retain 2 ltrs.	Yes	35	Practical Test piece packed	NA
16	Machine oil Bin cleaned	Yes	36	Fixture/s packed properly	NA
17	Coolant tank mesh cleaned & put back	Yes	37	Air removed from cover with Vaccum cleaner	NA
18	Chip Bin cleaned & put back	NA	38	Desiccant Bags Hung	NA
19	Chip Bin mesh cleaned & put back	NA	39	Fumigation Certificate available	NA
20	TPM points stickers fixed properly	NA	40		

REMARKS / SHORTAGES IF ANY.:

1] Electrical documentation Manuals & back up cd-roll

ASSEMBLY	STORES	FIXTURE	ELECTRICAL	DISPATCH	AUTHORISED SIGNATORY

Tajama

ACE MANUFACTURING SYSTEMS LTD.

AMS — In Pursuit of Excellence

DISPATCH CHECK POINTS

CUSTOMER'S NAME : Sakthi Auto component Ltd Erode.

MACHINE NUMBER : MV-805 MCV-400 DATE : 05-05-10

S.No	CHECK POINTS	STATUS - YES / NO	REMARKS
1	PACKING CASE IS IN GOOD CONDITION.	Yes	
2	CHIP CONVEYOR IS FREE FROM CHIPS & UNWANTED MATERIALS.	Yes	
3	PAINT SHOULD NOT BE PEELED OFF IN ANY PART OF THE MACHINE.	Yes	
4	ALL POCKETS IN ATC ARE EMPTY & CLEANED	Yes	
5	NO TOOL IN SPINDLE & CLEANED	Yes	
6	NO LOOSE PARTS KEPT ANYWHERE IN THE MACHINE.	Yes	
7	ENSURE RUST PREVENTIVE OIL IS APPLIED TO ALL MACHINED SURFACE.	Yes	
8	BOLT & NUT ARE FITTED AT ALL RELAVENT PLACES ON PACKING CASE.	Yes	
9	SPARE BOX KEPT INSIDE THE PACKING CASE.	Yes	
10	GEOMETRICAL, AXIS CALIBRATION, CUTTING TEST REPORTS ARE SENT WITH THE MACHINE Inside the cabinet	Yes	
11	ELECTRICAL CABINET CLEANED.	Yes	
12	ENSURE MACHINE IS CLEANED & NO DUST ON ANY WHERE ON M/c	Yes	
13	SUPRABHA COVER IS SEALED PROPERLY.	Yes	
14	ENSURE PACKING BOX SHOULD HAVE MINIMUM 3" GAP ALL OVER	Yes	
15	COOLANT WATER FROM ALL PIPES REMOVED BY AIR JET.	Yes	
16	NO RUST OBSERVED ANYWHERE IN THE MACHINE & RUST PREVENTIVE SPRAYED TO ALL FASTENERS & BLACKEDNED PARTS	Yes	
17	THERE IS NO TOUCHUP PAINT DEPOSITED ON MATCHING PARTS.	NO	
18	MACHINE LIFTING PROCEDURE CHART FIXED ON THE PACKING CASE	Yes	
19	CABINET KEY SENT WITH MACHINE TIED TO THE AC UNIT EYE BOLT	Yes	
20	PANEL COOLER FILTER IS CLEANED	Yes	
21	CHECK ITEMS AS PER PACKING LIST	Yes	
22	WOODEN PACKING PROVIDED BELOW THE APC STATION.	NO.	
23	WOODEN Support given bdow the grundfoss pump Mounting bracket	———	This proposal Letter dt 23/4/2011
24.	grundfoss pump Removed and packed seperately	Yes/NA	
25	MACHINE LIFTING PROCEDURE SKTCH PASTED ON THE GOURD	Yes	

ATTENDED BY QUALITY ASSURANCE DISPATCH - INCHARGE

F-PAC-02-R0

CONTROLLED COPY

Sign: M Date: 1/8

ACE MANUFACTURING SYSTEMS LTD

PACKING CASE IDENTIFICATION LIST

AMS

MACHINE NUMBER : MH-805 DATE : 05-05-12

SL.NO	CASE - 1 CONTENTS	QUANTITY
1	Machine Assembly	01 NO.
2	Std Spares and M/c Manuals	01 BOX
3	Leveling Screws and Lock Nut	4+4 NOS
4	Leveling Block 200 MM	08 NOS
5	Spin-Id-Oil	01 LTRS
6	Coolant Gun	01 NO.
7	Power Pack Pad	01 NO.
8	M/c Gourd	03 NOS
9		
10		
11		
12		

SL.NO	CASE - 2 CONTENTS	QUANTITY
1	Conveyor Assembly	01 NO.
2	Conveyor Pump	03 NO
3	Chip Tray	09 NOS
4	Oil bin	09 NOS
5	Oil Skimmer	01 NO.
6	Top Gourd	09 NOS
7	Mesh	08 NOS
8		
9		
10		
11		
12		

SL.NO	CASE - 3 CONTENTS	QUANTITY
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		

CHECKED BY :

ACE MANUFACTURING SYSTEMS LTD. M/C.Sl. No. M11-805

AMS
In Pursuit of Excellence

PACKING LIST ANNEXTURE-II **1032**

M/s, Sakthi Auto Component Ltd Erode

Sl.No.	DESCRIPTION	QTY.
1	O'Ring Dia 19.1X1.6	2
2	O' Ring Dia 8.1X1.6	6
3	O' RingDia 11.1X1.6	4
4	O'Ring Dia 57.6X2.4	6
5	O'Ring Dia 24.5x3.0	6
6	O'Ring Dia 51.6x2.4	2
7	Cord Of O'Ring Dia 3 X 2 Mtrs	1
8	Spanner 10 x 11	1
9	Spanner 12 x 13	1
10	Spanner 18 x 19	1
11	Spanner 30 x 32	1
12	Spanner 36 x 41	1
13	Allen key set Metric.	1
14	Extension Allen Key **8mm**	2
15	Split Collet With Stud Push	1
16	Fuse Set (Fanuc Make)	1
17	Glass Fuse Set (Kept in Electrical Cabinet)	1
18	IML-Process Oil - 12 (Kept in Machine) **Servo Spin-12**	20
19	Pull Stud BT-40 (**DIN,MAS 403**)	1
20	Fanuc Series Oi Mate Model D / Oi-Model D **USER`S MANUAL**	1
21	Fanuc Series Oi-Model D / Oi Mate Model D **MAINTENANCE MANUAL**	1
22	Fanuc AC SERVO & SPINDLE MOTOR **Bis series /alpha series** MAINTENANCE MANUAL	1
23	Operating Instructions And Maintainance Manual	1
24	Spare Parts Manual	1
25	Air Cooler Manual	
26		
27		
28		
29		
30		
31		
32		
33		
34		

Ace Micromatic Group Company

F-STR-27-R0

Sign..... DATE.....03-05-12

ACE MANUFACTURING SYSTEMS LIMITED.	AMS In Pursuit of Excellence
DISPATCH ADVICE	

Sl. No.	Description Of Dispatch details	
1	Customer Name	SAKTHI AUTO COMPONENT LTD., [Party Id - SAKAU001]
2	Telephone No.	04294 - 243401 to 4
3	Fax No.	04294 – 242268
4	E-Mail	sacl@sakthiauto.com
5	Customers ECC No.	AAECS 6536 JXM001
6	Customers Sales Tax No. & Date	CST: 727090 30/06/2000 TIN: 33241882293
7	Sales Order no.	MO10002325
8	Machine Model	MCV-400
9	Machine No.	M11-805
10	Invoice Address	SAKTHI AUTO COMPONENT LTD., [SAKAU001] MUKASI, PALLA GOUNDENPALAYAM ERODE RMS, PERUNDURAI VIA, PERUNDURAI - 638056
11	Place of Delivery	Default Address
12	Purchase Order No. & Date	SAL-PAL-Y11-CPO-A-200037 Date:30/03/2012
13	P.O Value (Excluding Taxes & Duties)	Rs.28,00,000.00
14	Transportation	Door delivery through any reliable carriers and freight to-pay basis.
15	Insurance	Will be arranged by the customer. Dispatch details to be faxed to the customer.
16	Scheduled Dispatch	07/05/2012
17	Payment	Refer payment collection detail sheet
18	Special Instructions	Keep the machine ready for dispatch. Contact HOD before dispatch Shortage list to be made while preparing machine Invoice All Pending Points to be attended before machine dispatch

Copy: Production/Electrical/Design/Purchase/Accounts/Dispatch/TSG

F-TSG-19-R1

For ACE MANUFACTURING SYSTEMS LTD.

Authorised Signatory 7/5/12

ACE MANUFACTURING SYSTEMS LIMITED		AMS
PACKING LIST		
PACKING LIST NO.	DNo#007475	Date: 03/05/2012
SALES ORDER NO.	MO10002325	Date: 31/03/2012
CUSTOMER	SAKTHI AUTO COMPONENT LTD., ERODE	
P.O. NO.	SAL-PAL-Y11-CPO-A-200037 Date : 30/03/2012	

Sl. No.	Item Id	Model	Qty
1	M11-805	MCV-400	1.000

Sl. No.	Description	Short Supply?
1	CNC Vertical Machining Center Model "MCV-400"	
	Spindle nose taper 7/24 No.40	
	Spindle power (Fanuc) 15 Min./Cont. Rating - 7.5 / 5.5 KW .	
	AC Servo axes drive (Fanuc)	
	20T-BT40-DIN Automatic tool magazine	
	Twin Arm (Random) type High Speed Auto tool changer	
	Tool shank BT-40	
	LM Guideways for all the three axes	
	CNC System Fanuc 0IMATE-MD with 8.4" Colour LCD	
	Ball screw stretching for X, Y & Z Axes	
	Panel cooler for electrical cabinet	
	Fail safe brake for Z-Axis	
	Standard work light	
	Coolant tank and chip tray	
	Three tier indication lamp	
	Flexible coupling for X, Y & Z Axes	
	Manual pulse generator	
	Rigid tapping	
	Total machine enclosure	
	Chip disposal to the rear side of the machine through two chutes on the sides	
	One set of manuals	
	Standard CNC features of Fanuc 0IMATE-MD with Colour LCD	
	Spindle speed of 60 - 6000 rpm (Indirect drive)	
	Rapid traverse of 30 / 30 / 30 m/min. for X, Y & Z Axes	
	Tool life management	
	Air drier unit (Small)	
2	Flood coolant system around the spindle	
3	Chip flushing system on the base	
4	Coolant gun	
5	Front auto door	
6	Increased day light area (NO increase in Z-stroke) - 125mm	
7	Magnetic chip conveyor for cast iron chips parallel to Y-Axis (2 Nos.)	
8	Screw conveyor	
9	4th Axis feature + Interfacing on the machine (only interface wiring)	
10	Wider guarding	
11	Hydraulic power pack for fixture - 4 station @ 45 bar pressure	

For ACE MANUFACTURING SYSTEMS LTD.

Authorised Signatory 7/5/12

12	Fixture interfacing with necessary M-codes	
13	Air seat check (2 nos.)	
14	Oil skimmer	
15	Component tray (2 nos.)	
16	Pull studs (20 nos.)	
17	SERVO SPIN - 12 lubricating oil (1 liter)	
18	1 set of glass fuses(inside the cabinet)	
19	Electrical documentation manual & back up CD	Yes
20	Geometrical test report	
21	NAS test report	
22	Laser Calibration test report	
23	Heavy cut & Rigid tapping test report	

For ACE MANUFACTURING SYSTEMS LTD.

Authorised Signatory 25/12

ACE MANUFACTURING SYSTEMS LIMITED

WORK ORDER

Customer : **M/s SAKTHI AUTO COMPONENT LTD.,** MUKASI, PALLA GOUNDENPALAYAM PERUNDURAI T.K, ERODE DIST ERODE 638056 TAMILNADU	**SO. No:** MO10002325 TO 2329	**WO. Date :** 05/04/2012
	PO. No.: SAL-PAL-Y11-CPO-A-200037	**PO. Date :** 30/03/2012
	S.O.TYPE: Standard	

Sl. No	Item Id	Item Description	Unit	Qty
1	VMC	CNC VERTICAL MACHINING CENTER - MCV-400	Nos	5

MACHINE COLOUR :

Machine Colour : ACE Blue & Light Grey combination.

WARRANTY :

a) One year (i.e. 12 months) from the date of commissioning of the machine or 15 months from the date of supply of the machine whichever is earlier against faulty material and workmanship. Guarantee is not applicable for part, which has normal wear & tear (like springs, balls etc.) and certain other items like Bulbs, Lamps, Indicator Lamps, Revolving Lamps, Seals and Glass Fuses.

b) For Fanuc CNC System, motors and drives, it is Two Years from the date of dispatch. This warranty is applicable only for the first installation of the machine.

Scope of Supply, Technical Specs & CNC Features As Per **Annexure I**

Machine Inspection	Geometrical accuracies and machine acceptable as per test chart and NAS test
Customer Inspection Type	Direct
Customer Inspection Date	2 Machines by 16/04/2012; 2nd Machines by 24/04/2012 & 1 Machine by 30/04/2012
Component Trials Required?	Not Applicable

FOR ACE MANUFACTURING SYSTEMS LTD.,

(P.RAMADAS)
MANAGING DIRECTOR

(L.S.UMESH)
CHIEF EXECUTIVE OFFICER

ACE MANUFACTURING SYSTEMS LTD.

PRODUCT SPECIFICATION SHEET

MODEL: MCV-400 - [5 NOS.]

Sl. No.	Description	Unit	MCV-400
1	**TABLE**		
1.1	TABLE SIZE	mm	900 x 450
1.2	T-SLOT DIM.	N x W x P	4 x 18 x 100
1.3	MAX. LOAD ON TABLE	Kgf	300
1.4	DIST. FROM FLOOR TO TABLE TOP	mm	925
2	**MACHINE CAPACITY**		
2.1	X - AXIS TRAVEL	mm	600
2.2	Y - AXIS TRAVEL	mm	450
2.3	Z - AXIS TRAVEL	mm	500
2.4	DIST. FROM SPINDLE FACE TO TABLE TOP WITH INCREASED DAY LIGHT AREA (125mm)	mm	**300 - 800**
2.5	DIST. FROM SPINDLE CENTER TO COLUMN GUIDEWAYS	mm	510
2.6	COOLANT SUPPLY-FLOOD COOLANT AROUND THE SPINDLE	lpm	**50**
3	**SPINDLE**		
3.1	SPINDLE NOSE TAPER		7 / 24 No.40
3.2	SPINDLE SPEED - INDIRECT DRIVE	rpm	60 - 6000
3.3	SPINDLE BEARING DIAMETER	mm	70
4	**FEED**		
4.1	RAPID TRAVERSE X, Y & Z AXES	m / min.	30 / 30 / 30
4.2	CUTTING FEED	mm / min.	1 - 10000
4.3	GUIDEWAYS FOR X, Y & Z AXES		Linear Motion
5	**AUTOMATIC TOOL CHANGER**		
5.1	NUMBER OF TOOLS	Nos.	20
5.2	MAX. TOOL DIA	mm	80
5.3	MAX. TOOL DIA. WITH ADJACENT POCKETS EMPTY	mm	155
5.4	TOOL SELECTION		Bi - Directional
5.5	TOOL LENGTH MAX.	mm	250
5.6	TOOL WEIGHT MAX.	Kg.	8
5.7	CHIP TO CHIP TIME (WITH Z ONLY / WITH X & Y ALSO)	Sec.	3.9 / 4.8
5.8	TOOL CHANGE SYSTEM		Twin Arm
5.9	TOOL SHANK TYPE		BT - 40
5.10	PULL STUD TYPE		DIN 69872 Form-B
6	**ACCURACY WITH ROTARY ENCODER**		
6.1	POSITIONING FOR X, Y & Z AXES AS PER VDI DGQ 3441	mm	0.015
6.2	POSITIONING FOR X, Y & Z AXES AS PER ISO 230-2	mm	0.010
6.3	REPEATABILITY FOR X,Y&Z AXES AS PER VDI DGQ 3441	mm	± 0.005
6.4	REPEATABILITY FOR X, Y & Z AXES AS PER ISO 230-2	mm	± 0.003
7	**MOTORS**		
7.1	SPINDLE POWER 15 MIN./CONT. (FANUC)	kW	7.5 / 5.5
7.2	FEED MOTOR X, Y & Z AXES (FANUC)	Nm	11 / 11 / 20

ACE MANUFACTURING SYSTEMS LTD.

PRODUCT SPECIFICATION SHEET

MODEL: MCV-400 - [5 NOS.]

Sl. No.	Description	Unit	MCV-400
8	**INSTALLATION DATA - STANDARD MACHINE**		
8.1	MACHINE WIDTH	mm	1900
8.2	MACHINE DEPTH	mm	3300
8.3	MACHINE HEIGHT	mm	2750
8.4	MACHINE WEIGHT - NET	Kgf	4100
8.5	POWER SUPPLY FOR BASIC MACHINE	Kva	14
8.6	CNC CONTROL (WITH 8.4" COLOUR LCD)		FANUC 0IMATE-MD
8.7	PNEUMATIC PRESSURE REQUIRED	Kgf / Cm2	5
8.8	PNEUMATIC SUPPLY REQUIRED AT ATMOSPHERIC PR.	Lpm	300
9	**TANK CAPACITY - STANDARD MACHINE**		
9.1	COOLANT TANK	litr	300 400
9.2	LUBRICATION TANK (USEFUL QUANTITY)	litr	5 (4)
10	**MACHINE FEATURES / ACCESSORIES - STANDARD**		
10.1	PANEL COOLER FOR ELECTRICAL CABINET		
10.2	FAIL SAFE BRAKE FOR Z - AXIS		
10.3	STANDARD WORK LIGHT		
10.4	COOLANT TANK & CHIP TRAY		
10.5	THREE TIER INDICATION LAMP TO INDICATE CYCLE RUNNING READY FOR NEXT CYCLE & MACHINE IN ALARM STATUS		
10.6	FLEXIBLE COUPLING FOR X, Y & Z AXES		
10.7	MANUAL PULSE GENERATOR		
10.8	RIGID TAPPING		
10.9	TOTAL MACHINE ENCLOSURE		
10.10	CHIP DISPOSAL TO THE REAR SIDE OF THE MACHINE THROUGH TWO CHUTES ON THE SIDES		
10.11	MANUALS - ONE SET		
10.12	BALL SCREW STRETCHING FOR X, Y & Z AXES		
10.13	TOOL LIFE MANAGEMENT		
10.14	AIR DRIER UNIT (SMALL)		
11	**STANDARD CNC FEATURES OF FANUC-0IMATE-MD**		
11.1	THREE CONTROLLED AXES		
11.2	SIMULTANEOUS CONTROLLABLE AXES - 3 AXES		
11.3	FEED RATE / RAPID OVERRIDE FACILITY		
11.4	CIRCULAR INTERPOLATION - ANY TWO OUT OF THREE AXES		
11.5	JOG MODE		
11.6	BACKLASH COMPENSATION		
11.7	PITCH ERROR COMPENSATION		
11.8	MANUAL DATA INPUT		
11.9	DRY RUN		
11.10	SINGLE BLOCK		
11.11	PROGRAM PROTECT KEY		
11.12	SELF DIAGNOSTIC FUNCTION WITH SYSTEM & MACHINE ALARM STATUS DISPLAY		
11.13	EMERGENCY STOP		
11.14	MIRROR IMAGE (X & Y CO-ORDINATES)		

ACE MANUFACTURING SYSTEMS LTD.

PRODUCT SPECIFICATION SHEET

MODEL: MCV-400 - [5 NOS.]

Sl. No.	Description	Unit	MCV-400
11.15	TOOL OFFSET MEMORY - 400 NOS.		
11.16	TOOL LENGTH COMPENSATION		
11.17	PART PROGRAM MEMORY 1280 MTS (512K) BATTERY BACKUP		
11.18	CUTTER DIAMETER COMPENSATION		
11.19	CANNED CYCLES FOR DRILLING, TAPPING AND BORING		
11.20	PROGRAMMABLE DATA INPUT (G10)		
11.21	HELICAL INTERPOLATION		
11.22	RIGID TAPPING		
11.23	CLOCK FUNCTION		
11.24	LOOK AHEAD CONTROL		
11.25	READER PUNCHER INTERFACE (RS 232)		
11.26	WORK CO-ORDINATE SYSTEM (G53 TO G59)		
11.27	ANGLE CHAMFERING / CORNER RADIUS		
11.28	CUSTOM MACRO-B		
11.29	CO-ORDINATE SYSTEM ROTATION		
11.30	NUMBER OF REGISTERED PROGRAMS TOTAL 200		
11.31	BACK GROUND EDITING		
11.32	EXTENDED PART PROGRAM EDITING		
11.33	RUN HOUR PARTS COUNT DISPLAY		
11.34	MANUAL PULSE GENERATOR		
11.35	ALARM HISTORY & OPERATION HISTORY		
11.36	SPINDLE LOAD DISPLAY		
12	**MACHINE FEATURES / ACCESSORIES - ADDITIONALLY ORDERED BY M/S SAKTHI AUTO COMPONENT LTD., ERODE.**		
12.1	FLOOD COOLANT SYSTEM AROUND THE SPINDLE		
12.2	CHIP FLUSHING SYSTEM ON THE BASE		
12.3	COOLANT GUN		
12.4	FRONT AUTO DOOR		
12.5	INCREASED DAY LIGHT AREA-125mm(NO INCREASE IN Z-STROKE)		
12.6	MAGNETIC CHIP CONVEYOR FOR CAST IRON CHIPS PARALLEL TO Y AXIS (2 NOS.)		
12.7	SCREW CONVEYOR		
12.8	4TH AXIS FEATURE + INTERFACING ON THE MACHINE (ONLY INTERFACE WIRING)		
12.9	WIDER GUARDING		
12.10	HYDRAULIC POWER PACK FOR FIXTURE - 4 STATION @ 45 BAR PRESSURE		
12.11	FIXTURE INTERFACING WITH NECESSARY M-CODES		
12.12	AIR SEAT CHECK (2 NOS.)		
12.13	OIL SKIMMER		
12.14	COMPONENT TRAY (2 NOS.)		

03-05-12

ACE MANUFACTURING SYSTEMS LTD

MACHINE SEQUENCE RUNNING TEST REPORT

AMS — In Pursuit of Excellence

MACHINE NUMBER : M11-805

Preconditions for Machine before starting Machine Sequence Running

1. Machine should be fitted with all accessories as per Work Order
2. Machine should be cleared from all Electrical & Mechanical Remarks
3. Machine should be run with Sufficient Coolant.
4. ATC should be full with tool holders
5. No Bypass of any Safety switches and cabinet sealed.

Date	Time	No of Hours Running	Date	Time	No of Hours Running	Remarks / Alarm Observed
28/01	2:07 PM	1 ✓			17 ✓	
		2 ✓			18 ✓	–
		3 ✓			19 ✓	
		4 ✓			20 ✓	
		5 ✓			21 ✓	
		6 ✓			22 ✓	
		7 ✓			23 ✓	
		8 ✓			24 ✓	
		9 ✓				
		10 ✓				
		11 ✓				
		12 ✓				
		13 ✓				
		14 ✓				
		15 ✓				
		16 ✓				

Nature of Remarks Related to	1.Hydraulic leakage	2. Coolant leakage	3.Electrical alarm	4. ATC	5. Spindle	6. Axes	7. Others

Note : In case M/c is stopped due to any reason, write the Sl. No. of the above remarks against corresponding number of hours, set right the M/c & continue to run for a total period of 24 hrs.

In charge - Mechanical **In charge - QA**

ACE MANUFACTURING SYSTEMS LTD

AMS *In Pursuit of Excellence*

SPINDLE TEMPERATURE STABILIZATION REPORT

M/c. NUMBER : MII-805	MAXIMUM RPM : 6000	DRIVE: ID/DD/IDCTS/DDCTS
SPINDLE SL No. : 10727	PULLEY RATIO : 1:1 / 1:1.25 / 1:1.5 /1:1.75 / 1:2	

Note : Refer TM-QA-07 for test procedure. **Recommended Temp. Rise : 20°C max. above ambient**

% of current drawn at max RPM of the spindle : (Recommended max : DD : β3 = ≤ 15%, β6 / α6 & above = ≤10%. ID : β3 = ≤ 20%, β6 / α6 & above = ≤15%.	Measured = 10 %
Spindle noise at max RPM [Recommended : 80 dB(A) upto 10 kW, 85 dB(A) for > 10 kW]	Measured = 78 dB (A)

SPINDLE RPM	TIME	AMBIENT TEMPERATURE	SPINDLE TEMPERATURE
500	3:00	33°C	—
	3:30	33°C	36°C
—	4:00	33°C	39°C
	4:30	33°C	41°C
	5.00	33°C	43°C
	5.30	33°C	45°C
	6.00	33°C	46°C
	6.30	33°C	47°C
	7.00	33°C	49°C

1. The Stabilization point, Calculated as follows. Is the Temperature at which the rate of temperature rise over 15 minutes is less than 5%.

= [(T2 – T1) / (T1 –Ta)] X 100

= < 5%

T1 = Previous Temp., T2 = Temp. after 15 Min & Ta = Ambient Temp. at T1



2. RUN SPINDLE AFTER STABILIZATION FOR 3 HOURS.

26/04/12	V. Gopal
Date	Checked By

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

MACHINE HEALTH CHECK POINTS

MACHINE NUMBER : M11-805 **DATE :** 26/04/12

I	**AXIS**	
1	Ensure plugs are fitted for L M Guide ways.	✓
2	Ensure effective wiping of saddle cover wipers.	NA
3	Ensure the lube timer is set 12 min for HG and 20 min for LM Guide ways.	✓
4	Ensure leveling bolts are fixed with locknut.	✓
5	Check the Table tenon slot 14H8 / 18H8 (Tolerance 0 to +0.027 mm)	✓
6	Ensure butt reference function.	✓
7	Check all the axes reference arrows are matched.	✓
8	Check Emergency push button function of Machine / APC / Double Hand	✓
9	Ensure marking of all screws with Yellow paint marker	✓
10	Ensure cover fixed to Index table, rotary joint & tool breakage sensor	NA
11	Ensure smooth movement of sliding door without play and unhealthy noise	✓
II	**SPINDLE**	
1	Ensure air jet through all the holes (4/8 holes) at oriented spindle position	✓
2	Ensure supply of air to spindle Air Purge system	NA
3	Check the tightness of push stud.	✓
4	Ensure grub screws are fitted to spindle flange.	✓
5	Check spindle orientation position and note down the value. (Parameter No. : 4031 for Fanuc controller, ... for Siemens controller)	1302
6	Ensure spindle balancing is completed	✓
7	Ensure presence of gap between draw bar bush & ejection screw / roller (visually or by feel)	✓
8	Check the "Tool not in spindle" proximity message.	✓
III	**ATC**	
1	Ensure ATC / APC / Counter balance bracket pinning.	✓
2	Ensure oil level is max. in ATC gear box.	✓
3	Check the Tool Number display on panel board is same as in spindle	✓
4	Check tool change position limit switch for proper functioning & band width (Max. 1.5 mm on each side).	✓

SURESHA F
CHECKED BY

ACE MANUFACTURING SYSTEMS LTD

MACHINE HEALTH CHECK POINTS

IV		COOLANT
1	✓	Ensure no coolant leakage around the machine & presence of coolant in lubrication oil drain pipe
2	✓	Ensure proper working of float switch (by shifting the sensor upwards).
3	✓	Check the function of Flood coolant (M7), Chip push (M182), Base flush (M181), CTS (M52) & Coolant gun (through selector switch).
4	N.A	Ensure drum wash in conveyors (Optional)
5	✓	Check conveyor overload message & Direction (Optional)
6	✓	Check oil in conveyor gear box. (Optional)
7	✓	Ensure functioning of screw conveyor in forward & reverse directions' (through selector switch).
8	N.A	Ensure CTS flow switch setting by opening the bag filter air vent ball valve (Optional)
9	N.A	Ensure suction strainer & Check Valve in CTS tank & pr. gauge functioning (Optional)
10	N.A	Ensure CTS pin locator hole is plugged (Optional)
11	N.A	Ensure that twin arm plunger & CTS pin locator screw do not foul (Optional)
12	N.A	Ensure bag filter clog message by closing bag filter outlet ball valve (Optional)
13	N.A	Ensure High pressure air blast after CTS switched off (Optional)
V		APC
1		Check pallet initialization in APC Machine
2	✓	Ensure supply of air jet to pallet rest pad cleaning.
3	✓	Ensure pallet change takes place smoothly with specified load (as per work order) without abnormal / unhealthy noise
VI		HYDRAULIC, PNEUMATIC & LUBRICATION
1	✓	Ensure air pressure switch is working properly.
2	✓	Ensure proper setting of oil (1 drop / tool change) in FRL unit & Oil Level low message
3	✓	Check the FRL drain hose is fixed.
4	✓	Ensure identification name plates are fixed on power pack hoses.
5	N.A	Check the Hyd.oil level low message (by adjusting sensor position) & Pr. gauge function
6	✓	Ensure hydraulic flow control valve grub locking in APC machine.
7	✓	Ensure Ball valve fixed to FRL Unit inlet
8	✓	Ensure no oil leakage in hydraulic valves & fittings
9	✓	Ensure lubrication pressure switch is set to 15 bar.
10	✓	Ensure pneumatic quick change coupling fixed to 4th axis provision
VII		GENERAL
1		Check all the points of MOM are attended.
2	✓	Ensure coolant tank capacity engraved or marked in name plate
3	✓	Check Hydraulic specification is as per circuit diagram
4	✓	Ensure axis calibration & ball bar parameter as per the report.
5	✓	Ensure Ball screw pitch in the machine and report is same.
6	✓	Ensure spindle Sl. No. and parameters are as per the report.

CHECKED BY

ACE MANUFACTURING SYSTEMS LTD.

AMS — In Pursuit of Excellence

MACHINE HEALTH CHECK POINTS

MACHINE No. : M11-805 ASSEMBLY TECHNICIAN : MT - Sreedhara

S.No	REMARKS OBSERVED	STATUS	SIGN
1	During Butt Refrence ay Refrence Bkt Folling to Table Baffle	L	03-05
2.	Lubrication tank pressure guage to be Replaced	L	03-05
(3)	componant Sect check solonoied mtg plate fixing	L	
(4)	Conveyor chip Bin to be positioned	L	0305
5	Conveyor codant Flash cover tobe Fixed	L	03-05
6.	Power pack Mtg Bkt supporting Bkt tobe Fixed	L	0305
7.	M/c Levelling Block to be Position	L	
8.	LH Side Conveyor Gear Box cover tobe Replaced	L	03-5
9.			

ASSEMBLY IN CHARGE

CHECKED BY 03-05-02

PAGE No. 3...3

F-QA-FA-09-R1

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

CHECK LIST - MECHANICAL

MACHINE NUMBER : M11-805 **DATE :** 26-04-12

I	Z-axis motor current during tool declamp (Turret type ATC) : Recommended Max : BT30-150%, BT40-180%)	
A	With Z axis moved at 840 mm/min in Jog mode	NA
B	In Auto cycle	

II Z - axis drop during power off :

- ve' direction< 0.005 mm		'+ ve' <0.015mm direction	
System Initial Reading :	-300.000	System Initial Reading. :	-800-000
System Final Reading :	-299.994	System Final Reading. :	-299.984
System Diff. in Reading :	0.006	System Diff. in Reading. :	0.016
600 Dial Reading. :	0.007	600 Dial Reading. :	0.018

III % of Axis current drawn (Recommended as per Data sheet DS -QA -02)

A	Axis	25 % Rapid Rate	50% Rapid Rate	100% Rapid Rate	600 mm/m Feed rate
	X	19%	23%	48%	17%
	Y	18%	21%	49%	20%
	Z Up	57%	59%	65%	54%
	Z Down	32%	34%	30%	33%
	B - Forward				
	B - Reverse				

B % of Axis holding current (Recommended as per Data sheet DS -QA -02)

Axis	100% Rapid Rate		2000 mm/min. Feed Rate	
	Motor end	Brake end	Motor end	Brake end
X	15%	-21%	1%	-1%
Y	22%	17%	6%	-2%
Z	56%	36%	44%	45%

C Over travel against Axis dead stopper in mm (Recommended as per Drawing)

Axis	Brake end	Motor End
X	26.311	20.719
Y	17.086	14.505
Z	26.250	6.450

IV SPINDLE

A	Push stud stroke length for Tool ejection (mm)	Recommended values	Auto	Manual
	BT – 30/40/50	Refer DS-DSN-PROD-01	0-7 mm	0-7 MM
	HSK A50/63/100		NA	NA
B	Tool clamping force-Kgf	Refer DS-DSN-PROD-01	9200kgf	

SURESHA T
CHECKED BY

C	Axial play in the spindle (Ref. TM-QA-10 for procedure) (Recommended max.except BT50 : 0.005 mm , for BT 50 : 0.008 mm)		
	1. Dial Reading. 'R1' (Ref. Step D)	0 ⟶ +0.036 ⟶ 0	Difference = mm (R1~R2) 2
	2. Dial Reading. 'R2' (Ref. Step G)	0 ⟶ -0.021 ⟶ -2	

V	Turret type ATC	
A	Check the spring lever compression at :	
	1. After the magazine butts against the dead stopper (mm)	
	2. Z – axis position below zero position (mm)	NA
	3. Recommended : BT 40 - 2.5 to 3 mm , BT 30 - 1.5 to 2 mm (i.e. 1-2)	
B	Tool picking position for Turret Type ATC Recommended : BT 40 - 60 to 80 mm , BT 30 - 50 to 65 mm	

VI	A.P.C	
A	Pressure setting for the pallet transfer cylinder in kg/cm^2 (As per circuit diagram)	
B	Pressure setting for the pallet clamp-de clamp in kg/cm^2 (As per circuit diagram)	NA

VII	Cycle Time in seconds (Refer Work order for recommended value)	
	1. Check the tool to tool time	2 Sec
	2. Check the chip to chip time with Z axis only	3.5 Sec
	3. Check the chip to chip time with all axes	4.85 Sec
	4. Check the pallet changing time	NA

CHECKED BY

CHECK LIST – MECHANICAL

AMS

1. MACHINE LEVEL READING :

Along X-Axis			Along Y-Axis		
0	¼	½	0	0	0
¼	0	¼	0	0	¼
½	0	0	0	¼	0

2. TABLE TOP READINGS:

Along X-Axis			Along Y-Axis		
0	-3	-3	0	+2	+6
0	-5	-4	-2	-3	-2
0	-4	-6	0	0	0

3. TENON SLOT READING :

0	-6

PALLET – II

NA

PALLET – II

Along X-Axis	Along Y-Axis
NA	NA

5. MANDREL READINGS:

Front	Side
-8	-10
0	0

RUNOUT:

a. TOP : (0.010mm)
1. 0.002

b. BOTTOM :(0.020mm)
1. 0.007
2. 0.007
3. 0.004
4. 0.006

6. TURN AROUND READING:



4.COLUMN READINGS :

FRONT	SIDE
13	17
0	0

7. SQUARENESS READING (X & Y):



8. PALLET HEIGHT VARIATION:

Pallet-1: N.A

Pallet-2 : N.A

NOTE: 1. For recommended value refer Design Data sheet DS-DSN-PROD-TC 01-06.

CHECKED BY

FANUC Series 0i Mate-M Model D　　DATA SHEET

得意先名:	FANUC INDIA PRIVATE LIMITED		
CUSTOMER:		DATE OF MANUFACTURE	:2011-12
CONTRACT NO.:	YD75814- 000	DATE OF TEST	:2011/12/20
MODEL NO.:	A02B-0321-B500	CHECKED BY	:A. Koike
SERIAL NO.:	E11Z51158	APPROVED BY	:MIYASAKA
SETTING OF INPUT:			

CNC IDENTIFICATION NUMBER

3C7B5D01
4991BCE5
5E34C389
4B92C47C

EDITION OF PRINTED BOARD & ROM

NAME	EDIT	NAME	EDIT	NAME	EDIT
A20B-8200-0849	01A	A02B-0319-H500#60W3	04		
		A02B-0319-H580#40B0	06		
		A02B-0319-J541#60VM	06		
		A02B-0319-J571#658E	05		
		A02B-0319-J572#658F	04		
		A02B-0319-J579#BW50	03		
		A02B-0320-J578#DX50	03		
		A02B-0320-J578#DX51	03		
		A02B-0322-H501#D5F1	21		
		A06B-6057-H507#90C5	06		

LIST OF CARD , DIMM & BACK BOARD

A20B-3300-0638	1				
A20B-3900-0286	1				
A20B-8002-0703	1				
A20B-8200-0560	1				

本データシートはファナック工場出荷時のCNC装置の装置情報です
Information contained in this Data Sheet is system configuration
at the time of FANUC factory shipment.

NAME	NAME	SPECIFICATION	ORDR
BASIC CONTROL UNIT	ベーシック ユニット	A02B-0321-B500	1
AXIS CONTROL CARD A2 FROM/SRAM MEMORY A1 MAIN BOARD POWER SUPPLAY UNIT DISPLAY UNIT NAME PLATE	ジク セイギョ カード A2 FROM/SRAMメモリ A1 メインボード デンゲン ユニット ヒョウジ ユニット メイバン	A02B-0319-H032 A02B-0319-H051 A02B-0319-H105 A02B-0319-H111 A02B-0319-H144#M A02B-0322-H190 A02B-0322-H202#512K	1 1 1 1 1 1
PACKAGE 3 CUSTOM SOFTWARE SIZE 512K BYTE MACRO EXECUTOR	パッケージ 3 カスタムソフト ヨウリョウ 512Kbyte マクロ エグゼキュータ	A02B-0322-H532 A02B-0322-J738#512K A02B-0322-J888 A02B-0322-J889	1 1 1
I/O UNIT FOR 0i	I/O UNIT	A02B-0309-C001	1
	SPINDLE AMP.	A06B-6164-H343#H580	1
	BIS12/3000 BIS12/3000 BIS22B/3000 SPB6/10000I	A06B-0078-B103 A06B-0078-B103#0100 A06B-0082-B403 A06B-1445-B103	1 1 1 1

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - MECHANICAL

AMS — In Pursuit of Excellence

MACHINE NUMBER : M11-0805 **DATE :** 28/04/12

1	ATC Details : Model	4020V / 4024V / 4030V / 4020H / 4024H /HSK A63 /HSK A100		
1.1	ATC :Turret Type/Twin Arm	Sl.No	15726	
1.2	Turret type magazine Encoder	Make	Model	Sl. No
		Pragati	ATC12 / ATC16 / ATC20	NA
1.3	ATC Torque Motor	TM 50 / 63 / 80 / 100 / 125 / Servo ATC		
2	**BELT / COUPLING DETAILS :**			
		GT Belt (For Indirect Drive)	COUPLING (For Direct Drive)	
2.1	Make	Unitta / Power Grip	Mayr	
2.2	Model			
3	**COOLANT SYSTEM DETAILS :**			
	Make : Rajmane Industries		Model	Type
3.1	Flood Coolant Pump - Crown/Flexinox/Disc Nozzle		RKM 206 / RV 160 - 270	Centrifugal Pump
3.2	~~Chip Pushing Coolant Pump~~ Screw conveyor		RKM 206 / RV 160 - 270	
3.3	Base Flushing Coolant Pump		RKM 206 / RV 160 - 270	
3.4	Coolant Gun & Drum Wash Pump		RKM 206 / RV 160 - 270	
3.5	Oil Skimmer - Make / Model	Rajmane	ROS3 40-300	
3.6	High Pressure Coolant Pump	N.A	Make	GF/ WP / BP
			Model	
3.7	Pressure Relief Valve		Make	Polyhydron
			Model	DPRH-10T-100-04
3.8	Rotary Joint		Make	Deublin / RIX
			Model	
4	**FLOAT SWITCH :**			
	Make		Filpro Electronics	
5	**CHIP CONVEYOR DETAILS :**			
5.1	Type of Conveyor	Scraper / Slat cum Scraper / Magnetic along X or Y axis.		
5.2	Model	UME. MC		
5.3	Make	~~Universal Conveyor~~ UNIMAG		
5.4	Sl.No	2012-0405 & 2012-0406		
6	**CONVEYOR GEAR BOX DETAILS :**			
6.1	Model	F25C		
6.2	Make	~~Universal Conveyor~~ SHAARC INDUSTRY		
7	**FILTER SPECIFICATIONS :**			
7.1	Model / Working pressure	8 /15, 50 bar / 100 bar		
7.2	Make	N.A Universal Conveyor		
7.3	Sl.No			
8	**COIL / SCREW CONVEYOR DETAILS :** Qty : 1 / 2			
8.1	Make	Universal Conveyor		
8.2	Model	Screw conveyor		

Checked By

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - MECHANICAL

AMS — In Pursuit of Excellence

9	HYDRAULIC SYSTEM :			
9.1	Make		Pascal / Hyd Tech / Rexorth / Yuken /Jai Chamundi /Hymech	
9.2	Product No		QC. No : JCT-003	
9.3	Tank Capacity (Litres)		32 / 40 / 63 / 70	
9.4	Maximum Working Pressure		50 BAR	
9.5	HYDRAULIC PUMP	Make Rexroth / yuken /Corotech / vickers	Model	
9.6	MOTOR	Make Rotomotive / Siemens	Model 90L-4-1400 / 90S-4-1390 ,	
10	PRESSURE SWITCHES FOR HYDRAULIC SYSTEM :			
10.1	Make		Polyhydron	
10.2	Model		IPS 30-50 / 30-100 / 10 - 30 /	
10.3	Quantity		04	
11	HYDRAULIC ACCUMULATOR :			
11.1	Make	FOX / BOSCH	FOX / BOSCH	
11.2	Set Oil Pressure	Tool de clamp :	Counter balance:	
11.3	Gas Pressure	Tool de clamp :	Counter balance:	
11.4	Volume (Litres)	Tool de clamp : 1.4	Counter balance : 4 or 10	
12	HYDRAULIC CYLINDERS :			
12.1	Make Island Hydraulics	Model Ø 40 X 22 X [125/152/180/1150]	Function Pallet Forward / Reverse	Qty
13	LUBRICATION UNIT DETAILS	Make CENLUB / DROPCO	Pressure Setting 15 Kg/ cm2	
14	FRL UNIT			
	Make Shavo / Festo / Norgan	Model MINI / MIDI	Operating Range 0-16 Kg/cm2	Grade of Oil Servo Mesh Spin 12
15	DRYER	Make Trident		Specification VXD - 2
16	PNEUMATIC VALVES			
16.1	Application Spindle Air Jet	Specs MFH 3-1/8	Make Festo	Qty 01
16.2	Spindle Air Purge	MFH 3-1/8	Festo	
16.3	ATC Pocket up & Down	JMFH 5- 1/8	Festo	01
16.4	Manual Tool De Clamp	MFH 5-1/8/JMFH 5-1/2	Festo	01
16.5	APC Auto Door	JMFH 5-1/8	Festo	
16.6	CTS Air Jet	MFH 3-1/8	Festo	
16.7	Front Auto Door	JMFH 5-1/8 MFH 3-1/8	Festo Festo	01 01
16.8	Pallet Rest Pad Cleaning	MFH 3-1/8	Festo	
16.9	Fixture		Festo	

Checked By

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - MECHANICAL

AMS — In Pursuit of Excellence

17	PRESSURE SWITCH FOR PNEUMATIC SYSTEM			
17.1	Operating Range		2 to 15 Kg /cm2	
17.2	Make		SUCO	
17.3	Quantity		1 + 1	
18	Tool de clamp system:		Mechanical / Pneumatic / Hydraulic / Hydro-Pneumatic	
	Function	Make	Model	Qty
18.1	Manual Tool De Clamp - Pneumatic	Festo	DNU 80-80-PPV DNU 100-80-PPV	1
		Rotex	SCN D -100 / 60 SCN D 80 / 80	1
18.2	Manual Tool De Clamp - Hydraulic	Island Hydraulic / AMS	ϕ40 X 20 X 65	1
18.3	Manual Tool De Clamp - Hydro pneumatic	Preac	PC33-8045-AM02	1
19	PNEUMATIC CYLINDERS USED			
	Function	Make	Model	Qty
19.1	Front Auto Door	Festo	DNC-32-400-PPV-A - 02	
19.2	APC Auto Door	Festo		
20	TURRET / INDEXING TABLE (OPTIONAL)			
	Make	Model	Sl.No	No of Station
	Pragathi / AMS		1	8 /12 /
21	ROTARY TABLE	Make	Model	Sl.No
		NIKKEN / UCAM		
22	TAIL STOCK 4th axis interface wiring only	Make	Model	Sl.No
23	PNEUMATIC COUNTER BALANCING			
23.1	Make	SMC / Rotex / Festo		
23.2	Cylinder Diameter :	Ø 80 / 100 / 125		
23.3	Air Reservoir used	Yes / No		
24	HYDRAULIC COUNTER BALANCING			
24.1	Make			
24.2	Model	Ø 50 X 32 X 670		

25	ADDITIONAL INFORMATION / REMARKS
1	
2	
3	

Checked By

1633

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - ELECTRICAL

AMS — In Pursuit of Excellence

M/C NO.: M11-805	DATE: 10/04/12
MODEL: MCV-400	CUSTOMER: Sakthi Auto Component.

M/C BACKUP (PATH) : \\arya2\E-Backup-II\ELECTRICAL MACHINE DATA\AMS DISPATCH MACHINE BACKUPS (20011-12)\FANUC 05.03

CNC SYSTEM

0i-MD ☐ 0i-MATE-MD ☑ ☐

PART No: A02B-0321-B500

Sl.No.: E11Z51158

SYSTEM OPTIONS:

β SERVO DRIVE SVPM

7.5i (20/20/40) ☐ 15i (40/40/80) ☑

PART No: A06B-6164-H343

Sl.No.: V11461464 #4580

α SERVO DRIVE PSM

11i ☐ 15i ☐ 26i ☐ ☐

PART No: A06B-

Sl.No.:

α SERVO DRIVE SPM

11i ☐ 15i ☐ 22i ☐ ☐

PART No: A06B-

Sl.No.:

α SERVO DRIVE SVM2

40/40i ☐ 80/80i ☐ 160/160i ☐

PART No: A06B-

Sl.No.:

α SERVO DRIVE SVM1(1'st)

40i ☐ 80i ☐ 160i ☐

PART No: A06B-

Sl.No.:

α SERVO DRIVE SVM1(2'nd)

40i ☐ 80i ☐ 160i ☐

PART No: A06B-

Sl.No.:

FANUC I/O MODULE / I/O CARD

I/O MODULE WITH MPG ☑	I/O CARD WITH MPG ☐	I/O CARD WITHOUT MPG ☑
PARTNo.: A02B-0309-C001	PART No.: A20B-2002-0520	PART No.: A20B-2002-0521
Sl No. E11X01031	Sl No.	Sl No.

AC REACTOR1

0.11mH/62A ☑ 0.07mH/110A ☐ ☐

PART No: A81L-0001-0156

Sl.No.: F11112003b

CHECKED BY:- [signature]

VERIFIED BY:- [signature]

F-QA-FA-14-R1

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - ELECTRICAL

AMS — In Pursuit of Excellence

SERVO MOTOR - X AXIS

β8/3K	β12/3K	β22/3K		PART No.:	SI.No.:
☐	☑	☐	☐	A06B-0078-B103 #100	C114B17F4

SERVO MOTOR - Y AXIS

β8/3K	β12/3K	β22/3K		PART No.:	SI.No.:
☐	☑	☐	☐	A06B-0078-B103	C114B0EDA

SERVO MOTOR - Z AXIS

β12/3K	β22/3K	β22/2K		PART No.:	SI.No.:
☐	☑	☐	☐	A06B-0082-B403	C112A0S2D

B AXIS DETAILS

ROTARY TABLE ☐ INDEX TABLE ☐ ☐

DRIVE:	βiSV-20	βiSV-40	PART No.:	SI.No.:
	☐	☐	A06B-____-H002	

MOTOR:	β4/4K	β8/3K	PART No.:	SI.No.:
	☐	☐	A06B-0___-____	

REACTOR: A81L-0001-0083#3C (0.15mH/24A) ☐ SI No.:

DISCHARGE RESISTOR: 16Ohms ☐ 30Ohms ☐

PMM AXIS DETAILS

SERVO ARM ☐ SERVO MAG ☐ NA TILTING TABLE ☐

DRIVE:	βiSV-20	βiSV-40	PART No.:	SI.No.:
	☐	☐	A06B-____-H002	

MOTOR:	β4/4K	β8/3K	PART No.:	SI.No.:
	☐	☐	A06B-0___-____	

REACTOR: A81L-0001-0083#3C (0.15mH/24A) ☐ SI No.:

DISCHARGE RESISTOR: 16Ohms ☐ 30Ohms ☐

SPECIAL INFORMATIONS:

→ Rotary Table only electrical interfacing wiring.

CHECKED BY:- VERIFIED BY:-

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - ELECTRICAL

AMS — In Pursuit of Excellence

ISOLATTION SWITCH (SW1) — AC 3 Ph 415V ☑

40A ☑ 63A ☐ 100A ☐

MAKE: SALZER ☑ ABB ☐ ☐

TYPE:

ISOLATTION TRANSFORMER (TFR1) PRIMARY- 415V/3Ph SECONDARY - 220V/3Ph

10KVA ☐ 12KVA ☑ 15.5KVA ☐ ☐

MAKE: SALZER ☐ T.S INTERNATIONAL ☑

SL.No: 7094-03-12

PRIMARY MCB (F15) — AC 3 Ph 415V / 3POLE ☑

25A ☑ 32A ☐ 40A ☐ ☐

MAKE: SCHNEIDER ☑ MERLIN GERIN ☐

TYPE:

SECONDARY MCB (F19) — AC 3 Ph 220V / 3POLE ☑

40A ☐ 50A ☑ 63A ☐ ☐

MAKE: SCHNEIDER ☑ ABB ☐

TYPE:

DRIVE CONTROL MCB (F20) N/A — AC 3 Ph 220V / 2POLE ☐

1A ☐ 3A ☐ ☐ ☐

MAKE: SCHNEIDER ☐ MERLIN GERIN ☐

TYPE:

SPINDLE MOTOR FAN MPCB (F56) — AC 3 Ph 220V / 3POLE ☑

0.1-0.16A ☑ 0.25-0.4A ☐ ☐

MAKE: ABB ☐ SPRECHER &SCHU ☑

MPCB SETTING: 0.10A

PSM CONTACTOR (K19) — 2 30V AC ☑

CA3-30-10 ☐ A -30-10 ☐ CA3-37-N-11 ☑ ☐

MAKE: ABB ☐ SPRECHER &SCHU ☑

TYPE:

REGULATED POWER SUPPLY DETAILS

PS1 ☑ PS2 ☑ PS3 ☐

OUTPUT: 24V DC 10A ☑ 24V DC 20A ☐

MAKE: SCHNEIDER(ABL 1RPM24100) ☐ OMRON(S8VE 24024) ☑ KB ELECTORNICS ☐

Sl. No.: PS1: PS2: PS3:

ISOLATTION TRANSFORMER (TFR4) PRIMARY- 415V/1Ph SECONDARY - 200V/1Ph

900VA ☑ 1.5KVA ☐ ☐

MAKE: SALZER ☐ T.S INTERNATIONAL ☑

SL.No: 3706-03-12

TFR4 PRIMARY MCB (F16) : 3A/2P ☑ ☐ — MAKE:SCHNEIDER ☑ MERLIN GERIN ☐

TFR4 SEC. MCB (F58) : 6A/1P ☑ ☐ — MAKE:SCHNEIDER ☑ MERLIN GERIN ☐

TFR4 SEC. MCB (F59) : 2A/1P ☑ ☐ — MAKE:SCHNEIDER ☑ MERLIN GERIN ☐

SPECIAL INFORMATIONS:

CHECKED BY:- 05/12

VERIFIED BY:-

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - ELECTRICAL

AMS — In Pursuit of Excellence

CONTROL CIRCUIT

SEALED KEY BOARD/MCP: Sl.No.: 1633

TYPE: (YSL-AMS-SKB-2-REV1-10/09) ☑ YSL-SPARK-MCP2-REV2-05/05 ☐

ATC BRAKE RELAY (PCB 1) :

TYPE: 4 SSR RELAY -YSL-SSRP-BR-3-REV1-06/10 ☑ 2 SSR RELAY - YSL-S26-009-77-REV0-08/10 ☑

I/O DISTRIBUTON PCB (PCB 2) : Sl.No.:

TYPE: YSL-S26-009-56-REV0-04/08 ☑ YSL IFB- 50-FCC TB - REV3 01/06 ☐

CNC ON/OFF RELAY (PCB 3) :

TYPE: YSL -SSR-CNC ON / OFF-REV8-08/10 ☑

Z AXIS BRAKE RELAY (PCB 5) :

TYPE: YSL-SSRP-BR3-REV1-06/10 ☑

Z AXIS BRAKE CURRENT SENSINGRELAY (CSR1) :

TYPE: YSL ELECTRONICS (CSR1-2) ☑

AC RELAYS: Z BRAKE/EMG (ACR1) ☑ ATC/CAB. THERMAL(ACR2) ☑ I. TABLE THERMAL(ACR3) ☐

MAKE: : OMRON ☑ ELESTA ☐

RELAY BOARD(STD-X20) 1RELAY(ELECTRO MAGNETIC-DC) ☑

TYPE: YSL-UMK-1RM-24V- DC-CN-FI-2-REV1-12/09 ☑

RELAY BOARD(STD-X31) 1RELAY(ELECTRO MAGNETIC-DC/AC) ☑

TYPE: YSL-S26-009-082-REV1-06/10 ☑

RELAY BOARD(APC-X25) 8 RELAY (SSR TYPE-DC) ☐

TYPE: YSL-S26-009-064-REV3-08/08 ☐

RELAY BOARD(FIXTURE-X26) 2 / 4 / 8 RELAY (SSR TYPE-DC) ☑

TYPE: YSL-S26-009-062-REV3-08/08 ☐ S26-009-063-REV3-08/08 ☐ S26-009-064-REV3-08/08 ☑

RELAY BOARD(TOOL DECLAMP - X33) 1 RELAY (SSR TYPE-DC) ☐

TYPE: YSL-S26-009-061-REV3-08/08 ☐

RELAY BOARD(-X 29) 1 RELAY (SSR TYPE-DC) ☑

TYPE: YSL-S26-009-061-REV3-08/08 ☑

EMERGENCY CONTACTOR (K22) 24V DC ☑

CS8C-40E ☑ KC6-40E ☐	MAKE: ABB ☐ SPRECHER &SCHU ☑
	TYPE:
CHECKED BY:-	VERIFIED BY:-

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - ELECTRICAL

AMS — In Pursuit of Excellence

POWER FAILURE DETECTION MODULE (PFDM) : 24V DC ☐

MAKE: YSL-3PFMR-2 ☐

CAPACITOR BANK (DP1) : 24V DC ☑

MAKE: YSL-PF-CHU-1 ☑

SINGLE PHASE POWER SUPPLY CIRCUIT

MCB (F18) AC 1 Ph 230V / 1POLE ☑

10A ☑ ☐ ☐

MAKE: SCHNEIDER ☑ MERLIN GERIN ☐

TYPE:

PANEL COOLER: POWER: 500W ☐ 1000W ☐

MAKE: ADVANCE (TURBO1000R33) ☑ ADVANCE (TURBO500R50) ☐ ACE (IGLOO - 750) ☐

Sl.No.: 43558-03-12

UTILITIES (CABINET):

CABINET LAMP: PEARL(CFL-11W) ☑ PHILIPS(CFL-11W) ☐ ☐

GANG BOX: 2 SWITCHES + 1SOCKET + I INDICATOR ☐

DOOR INTERLOCK: LIMIT SW (HONEYWELL-ZLD A01D) ☑

MCB FOR CAB. LAMP, 5 PIN SOCKET (F66-3A/1PMAKE: SCHNEIDER) ☑

UTILITIES (SWITCHGEARS):

ADD ON BLOCK(PCB5/PSM(K19) INTERLOCK): SPC&SCH(CS7-PV) ☐ SPC&SCH(CA3-P) ☐

ADD ON BLOCK(STAR DELTA INTERLOCK): SPC&SCH(CS7-PV) ☐ SPC&SCH(CA3-P) ☐

ADD ON BLOCK(HYDRAULIC FAN POWER): (K9) SPC&SCH(CS8-P22Z) ☑ ABB(CAF6-20-M) ☐

ADD ON BLOCK(AUTO DRAIN SOL): (K4) SPC&SCH(CS8-P22Z) ☑ ABB(CAF6-20-M) ☐

SPINDLE STAR / DELTA CIRCUIT

CONTACTORS (K20 / K21) N/A 230V AC ☐

CA3-72N-L11 ☐ CA7 - 85 ☐ ☐

MAKE: ABB ☐ SPRECHER &SCHU ☐

TYPE:

RELAY BOARD(X32) 2 RELAYS (SSR TYPE) ☐

TYPE: S26-009-80-CN--F-24DC-230AC ☐

SPECIAL INFORMATIONS: Note ① TM.A01-01-04-M00

Logic C1-A-00 A2.02-01

K1-A-00 B2-2-01

M2A-00

CHECKED BY:- VERIFIED BY:-

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - ELECTRICAL

AMS — In Pursuit of Excellence

MAGAZINE MOTOR POWER

MPCB (F1)	1-1.6A	☑	☐	CONTACTOR (K1/K2)	CA8-9C	☑	VBC6-30-01 ☐
MPCB SETTING:	1A	☑	☐	MOTOR POWER:	1.1KVA/1.5A	☑	1.6KVA/2.3A ☐
SOLID STATE RELAY (SSR1):				MAKE: ERI ELECTRONICS- SJDA - 482524(DSPST)			☑

ARM MOTOR POWER

MPCB (F2)	1-1.6A	☑	☐	CONTACTOR (K3/K76)	CA8-9C	☑	VBC6-30-01 ☐
MPCB SETTING:	1A	☑	☐	MOTOR POWER:	1.1KVA/1.5A	☑	2.3KVA/3.2A ☐
SOLID STATE RELAY (SSR3):				MAKE: ERI ELECTRONICS- SJDA - 482524(DSPST)			☑

LUBRICATION MOTOR POWER

MCB (F3)	1A/3P	☑	MPCB(0.63-1A) ☐	CONTACTOR (K4)	CA8-9C	☑	BC6-30-01 ☐
				MOTOR POWER:	0.09KW/0.5A	☐	0.12KW/0.6A ☑

FLOOD COOLANT MOTOR POWER

MPCB (F4)	0.63-1A	☑	2.5-4A ☐	CONTACTOR (K5)	CA8-9C	☑	BC6-30-01 ☐
MPCB SETTING:	0.9A	☑	3.4A ☐	MOTOR POWER:	0.37KW/0.9A	☑	1.5KW/3.4A ☐
SURGE SUPRESSOR(RC4):				YSL-NIR-RC3-1/022-575VAC			☑

CHIP PUSH COOLANT MOTOR POWER

MPCB (F5)	0.63-1A	☐	2.5-4A ☐	CONTACTOR (K6)	CA8-9C	☐	BC6-30-01 ☐
MPCB SETTING:	0.9A	☐	3.4A ☐	MOTOR POWER:	0.37KW/0.9A	☐	1.5KW/3.4A ☐
SURGE SUPRESSOR(RC5): YSL-NIR-RC3-1/022-575VAC ☐				COMMON CONTACOR KIT - PUSH/FLUSH(ABB-VBC6)			☐

CHIP FLUSH COOLANT MOTOR POWER

MPCB (F6)	0.63-1A	☐	2.5-4A ☑	CONTACTOR (K7)	CA8-9C	☐	BC6-30-01 ☐
MPCB SETTING:	0.9A	☐	3.4A ☑	MOTOR POWER:	0.37KW/0.9A	☐	1.5KW/3.4A ☑
SURGE SUPRESSOR(RC6): YSL-NIR-RC3-1/022-575VAC ☑				COMMON MPCB WITH CHIP PUSH			☐

COOLANT GUN MOTOR POWER

MPCB (F27)	0.63-1A	☑	2.5-4A ☐	CONTACTOR (K25)	CA8-9C	☑	BC6-30-01 ☐
MPCB SETTING:	0.9A	☑	3.4A ☐	MOTOR POWER:	0.37KW/0.9A	☑	1.5KW/3.4A ☐
SURGE SUPRESSOR(RC27):				YSL-NIR-RC3-1/022-575VAC			☑

HIGH PRESSURE COOLANT MOTOR POWER

MPCB (F9)	4-6.3A	☐	2.5-4A ☐	CONTACTOR (K10)	CA8-12C	☐	BC7-30-01 ☐
MPCB SETTING:	4.9A	☐	5.2A ☐	MOTOR POWER:	2.2KW/4.9A	☐	2.2KW/5.2A ☐
SURGE SUPRESSOR(RC9):				YSL-NIR-RC3-1/022-575VAC			☐

HYDRAULIC 1 MOTOR POWER

MPCB (F8)	4-6.3A	☐	2.5-4A ☑	CONTACTOR (K9)	CA8-9C	☑	BC6-30-01 ☐
MPCB SETTING:	2.7A	☑	3.5A ☐	MOTOR POWER:	1.1KW/2.7A	☑	1.5KW/3.5A ☐
SURGE SUPRESSOR(RC8):				YSL-NIR-RC3-1/022-575VAC			☑

CHECKED BY:- [signature]

VERIFIED BY:- [signature]

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - ELECTRICAL

AMS — In Pursuit of Excellence

INDEX TABLE MOTOR POWER

MPCB (F12)	2.5-4A ☐	☐	CONTACTOR(K15/K16) CA8-9C ☐	VBC6-30-01 ☐	
MPCB SETTING:	☐	☐	MOTOR POWER:	☐ 1.6KVA/2.3A	☐
SOLID STATE RELAY (SSR5):			MAKE: ERI ELECTRONICS- SJDA - 482524(DSPST) ☐		

CHIP CONVEYOR 1 MOTOR POWER (Mag. Conv)

MPCB (F10)	0.63-1A ☑	1-1.6A ☐	CONTACTOR(K11/K12) CA8-9C ☑	VBC6-30-01 ☐	
MPCB SETTING:	0.74A ☐	0.8A ☑	MOTORPOWER: 0.18KW/~~0.65A~~ 0.7A ☑		☐
SURGE SUPRESSOR(RC10):			YSL-NIR-RC3-1/022-575VAC		☑

CHIP CONVEYOR 2 MOTOR POWER (Mag. Conv)

MPCB (F11)	0.63-1A ☑	1-1.6A ☐	CONTACTOR(K13/K14) CA8-9C ☑	VBC6-30-01 ☐	
MPCB SETTING:	0.74A ☐	0.8A ☑	MOTORPOWER: 0.18KW/~~0.65A~~ 0.7A ☑		☐
SURGE SUPRESSOR(RC11):			YSL-NIR-RC3-1/022-575VAC		☑

CONVEYOR DRUM WASH MOTOR POWER

MPCB (F7) N/A	0.63-1A ☑	2.5-4A ☐	CONTACTOR (K8) CA8-9C ☑	BC6-30-01 ☐	
MPCB SETTING:	0.9A ☐	3.4A ☐	MOTOR POWER: 0.37KW/0.9A ☐	1.5KW/3.4A ☐	
SURGE SUPRESSOR(RC7):			YSL-NIR-RC3-1/022-575VAC		☑

SCREW CONVEYOR 1 MOTOR POWER

MPCB (F13)	0.63-1A ☐	1-1.6A ☑	CONTACTOR(K17/K18) CA8-9C ☑	VBC6-30-01 ☐	
MPCB SETTING:	0.74A ☐	1.4A ☑	MOTORPOWER: 0.18KW/0.65A ☐	0.37KW/1.1A ☑	
SURGE SUPRESSOR(RC13):			YSL-NIR-RC3-1/022-575VAC		☑

SCREW CONVEYOR 2 MOTOR POWER

MPCB (F30)	0.63-1A ☐	1-1.6A ☐	CONTACTOR(K28/K29) CA8-9C ☐	VBC6-30-01 ☐	
MPCB SETTING:	0.74A ☐	1.4A ☐	MOTORPOWER: 0.18KW/0.65A ☐	0.37KW/1.1A ☐	
SURGE SUPRESSOR(RC30):			YSL-NIR-RC3-1/022-575VAC		☐

MOTOR POWER (OPTIONAL-1)

MPCB (F21) 0.25-0.4A	☑	☐	CONTACTOR (K23) CA8-9C ☑	BC6-30-01 ☐	
MPCB SETTING:	☐	0.3A ☑	MOTOR POWER: 0.04KW/0.3A ☑		☐
SURGE SUPRESSOR(RC):			YSL-NIR-RC3-1/022-575VAC		☑

MOTOR POWER (OPTIONAL - 2)

MPCB (F)	☐	☐	CONTACTOR (K) CA8-9C ☐	BC6-30-01 ☐	
MPCB SETTING:	☐	☐	MOTOR POWER: ☐		☐
SURGE SUPRESSOR(RC):			YSL-NIR-RC3-1/022-575VAC		☐

SPECIAL INFORMATIONS: MPCB'S- SPRECHER &SCHU(KTA7-25S) ☑ ABB (MS 116) ☐

CHECKED BY:- [signature]

VERIFIED BY:- [signature]

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - ELECTRICAL

AMS — In Pursuit of Excellence

ATC & SPINDLE DETAILS

SPINDLE MOTOR:	MODEL:	β3 ☐	β6 ☑	β12 ☐	☐
	MOTOR RPM:	6000 ☐	8000 ☐	10000 ☑	☐
	MOTOR POWER:	7.5/5.5 KW			
	PART No:	A06B-1445-B103			
	Sl. No:	C4Z30020			
	GEAR RATIO:	1:1 ☐	1:1.25 ☐	1:1.5 ☑	DIRECT DRIVE ☐
	POWER LIMIT:	IN KW:			
	SPEED LIMIT:	IN RPM: 60–6000rpm			

PROXIMITY SENSORS-SPINDLE

MAKE; TEKNIC ☑ TYPE: (24V DC - PNP) ☑

SPINDLE ORIENTATION (PXS1) ☑		M12X40	M12X52	M12X68	M12X73
TYPE:	CONNECTOR ☑ NON CONN. ☐	☐	☐	☐	☑
TOOL CLAMP(PXS3) ☑		M12X40	M12X52	M12X68	M12X73
TYPE:	CONNECTOR ☑ NON CONN. ☐	☐	☐	☐	☑
TOOL DECLAMP(PXS4) ☑		M12X40	M12X52	M12X68	M12X73
TYPE:	CONNECTOR ☑ NON CONN. ☐	☐	☐	☐	☑
NO TOOL IN SPINDLE(PXS32) ☑		M08X50	M08X68	M12X73	
TYPE:	CONNECTOR ☑ NON CONN. ☐	☐	☑	☐	☐
ONE ROTATION(PXS39) ☑		M12X40	M12X52	M12X68	M12X73
TYPE:	CONNECTOR ☑ NON CONN. ☐	☐	☐	☐	☑

PROXIMITY SENSORS-ATC(DISC TYPE)

MAKE; TEKNIC ☐ TYPE: (24V DC - PNP) NA ☐

MAGAZINE IN POSITION (PXS2) ☐		M12X40	M12X52	M12X68	M12X73
TYPE:	CONNECTOR ☐ NON CONN. ☐	☐	☐	☐	☐
MAGAZINE REFERENCE (PXS46) ☐		M12X73	FG2X05APO24-5000LFLAT		
TYPE:	CONNECTOR ☐ NON CONN. ☐	☐	☐		☐

PROXIMITY SENSORS-ATC(TWIN ARM TYPE)

MAKE; TEKNIC ☑	TYPE:EGT 12 X 02 AP - 024 SEM4L(24V DC - PNP) ☑
MAGAZINE IN POSITION PROXIMITY (PXS2) ☑	MAG REFERENCE PROXIMITY (PXS46) ☑
POCKET UP PROXIMITY (PXS5) ☑	POCKET DOWN PROXIMITY (PXS6) ☑
ARM POSITION 1 PROXIMITY-PS1 (PXS7) ☑	☐
ARM POSITION 2 PROXIMITY-PS2 (PXS58) ☑	ARM POSITION 3 PROXIMITY-PS3 (PXS59) ☑

CHECKED BY:- K.V. Sankar

VERIFIED BY:-

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - ELECTRICAL

AMS — In Pursuit of Excellence

PNUEMATIC ELEMENTS (SPINDLE + ATC)

MAKE; SUCO ☑	TYPE:(24V DC - NO CONTACT) ☑
MAIN AIR PRESSURE SWITCH (PRS 2) ☑	SPINDLE AIR PRESSURE SWITCH (PRS 101) ☑
AIR PURGE PRESSURE SWITCH (PRS 102) ☐	☐
MAKE; FESTO ☑ SMC ☐	TYPE:(24V DC -COIL) ☑
SPINDLE AIR JET SOLENOID (Y1) ☑	SPI AIR PURGE SOLENOID (Y115) ☐
POCKET UP SOLENOID (Y2) ☑	POCKET DOWN SOLENOID (Y3) ☑
TOOL CLAMP SOLENOID (Y51) ☑	TOOL DECLAMP SOLENOID (Y4) ☑
AIR THROUGH NOZZLE SOLENOID (Y99) ☐	☐

HYDRAULIC ELEMENTS (SPINDLE + ATC) NA

MAKE; YUKEN ☐ REXROTH ☐	TYPE:(24V DC -COIL) ☐
☐	TOOL DECLAMP SOLENOID (Y4) ☐

UTILITIES(SPINDLE + ATC)

TOOL CHANGE POSITION LIMIT SWITCH- (LS3) :	TEKNIC SG-01-R-610 ☑	☐
TOOL DECLAMP PUSH BUTTON :	ILLUMINATED GREEN ☑	☐
ATC / I.TABLE DISPLAY SEL SWITCH :	2 POSITION ☐	☐
MAG TEST MODE KEY SWITCH (KSW7) :	2 POSITION ☐	☐
	☐	☐

SPECIAL INFORMATIONS: → Seat check prsw (smc make) - PRS 48 & PRS 50
→ Door check Door.

AUTO DOOR & CYCLE START DETAILS

MAKE; FESTO ☑	TYPE:(24V DC -COIL) ☑
AUTO DOOR OPEN SOLENOID (Y6) ☑	AUTO DOOR CLOSE SOLENOID (Y7) ☑
AUTO DOOR SAFETYSOLENOID (Y8) ☑	☐
DOOR SWITCHES MAKE; TECNIK ☐ FESTO ☑	TYPE: LS5 - NG1 RS 510 (24V DC -NO CONTACT) ☐ READ SWITCHES (RSW30& RSW31) ☑
CYCLE START SWITCH MAKE; ☐ TELEMECHANIC ☐	TYPE: LS45 - XCE-154 (24V DC -NO CONTACT) ☐ ☐
DOUBLE HAND CYCLE START BOX MAKE; TECNIK ☑ ☐	CYCLE START PB (MUSHROOM HEAD GREEN) (02 Nos) ☑ EMERGENCY PB (MUSHROOM HEAD SPRING RETURN) ☑
AUTO DOOR OPERATION MAKE; TECNIK ☑ ☐	AUTO DOOR OPEN/CLOSE PB (GREEN) ☑ AUTO DOOR INTERLOCK KEY SW (2 POSITION) ☑

SPECIAL INFORMATIONS:

CHECKED BY:- K.V.Hari Prasad **VERIFIED BY:-**

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - ELECTRICAL

AMS — For Pursuit of Excellence

COOLANT TANK / CONVEYORS DETAIL

UTILITIES (STD COOLANT)

COOLANT LEVEL FLOAT SWITCH (PXS 8) :	FILPRO(LIM 18PF SC)	☑		☐	
COOLANT GUN SEL SW :	2 POSITION	☑		☐	
FLUSH COOLANT VALVE (Y128) :	AVCON	☐		☐	
COOLANT PLUG (HC1) :	16 PIN	☐		24 PIN	☑
LOCATION(FROM M/C REAR) :	LHS	☐		RHS	☑

UTILITIES (HP COOLANT): NA

FLOW SWITCH (FLW1) :	IFM (SH0 500)	☐		☐	
CLOG SWITCH (FCLG1) :	HIRLEKAR	☐		SALVIN	☐
AIR BLAST SOLENOID (Y5) :	FESTO	☐		☐	
M/C DOOR CLOSE LIMIT SW (LS5) :	TEKNIC(NG1 RS 510)	☐		☐	

UTILITIES (CHIP CONVEYOR):

CHIP CONVEYOR 1 O/L LIMIT SW (LS12) :	BOHMEN TEKNIC(NG1 RS 510)	☑		☐	
CHIP CONVEYOR 2 O/L LIMIT SW (LS13) :	BOHMEN TEKNIC(NG1 RS 510)	☑		☐	
CHIP CONVEYOR FWD/REV SEL SW :	3 POSITION(SPRING RETURN)	☑		☐	
CHIP CONVEYOR PLUG (HC3) :	10 PIN	☑		24 PIN	☐
LOCATION(FROM M/C REAR) : (T)	LHS	☑	(T)	RHS	☑

UTILITIES (SCREW CONVEYOR):

SCREW CONVEYOR 1 O/L PROXIMITY (PXS20) :	M12 X 52MM (CONN. TYPE)	☐		M12 X 72MM (CONN. TYPE)	☑
SCREW CONVEYOR 2 O/L PROXIMITY(PXS104) :	M12 X 52MM (CONN. TYPE)	☐		M12 X 72MM (CONN. TYPE)	☑
SCREW CONVEYOR FWD/REV SEL SW :	3 POSITION(SPRING RETURN)	☐		COMMON WITH CHIP.CNYR	☑

SPECIAL INFORMATIONS:

HYDRAULIC TANK DETAIL

OIL LEVEL FLOAT SWITCH (FL4) :	SHRIDHAN	☐		☐	
OIL CLOG SWITCH (CLG2) :	HYDAC	☐		☐	
HYDRAULIC THERMAL SWITCH (TH4) :	CARE SYSTEM	☐		☐	
HYDRAULIC PLUG (HC2) :	16 PIN	☐		24 PIN	☑
MAKE;INDO ELECTRIC ☑ LOCATION(FROM M/C REAR) :	LHS	☑		RHS	☐

SPECIAL INFORMATIONS:

CHECKED BY:- K.V. Yadav

VERIFIED BY:-

ACE MANUFACTURING SYSTEMS LTD

MACHINE HISTORY - ELECTRICAL

AMS *In Pursuit of Excellence*

LUBRICATION TANK / FRL DETAIL

OIL LEVEL FLOAT SWITCH (FL1) :	CENLUB	☑	☐
LUB PRESSURE SWITCH (PRS1) :	SUCO	☑	☐
AUTO DRAIN SOLENOID (Y44) :	ROTEX	☑	☐

MACHINE LAMPS

MAKE:			PATANKAR	☐	AISHWARYA ☑
MACHINE LAMP1 (ML1) :	11W	☐	9W+9W	☐	36W ☑
MACHINE LAMP2 (ML2) :	11W	☐	9W+9W	☐	36W ☑
MACHINE LAMP3 (ML3) :	11W	☐	9W+9W	☐	36W ☐
MAHINE INDICATION LAMP(PL5) :	1 TIER	☐	3 TIER	☑	3 TIER WITH HOOTER ☐
MAKE:			PATANKAR	☑	LAXMI(VANTECH) ☐

UTILITIES(MAHINE)

EMERGENCY MONITOR (PCB 12)			YSL-EMG-PCB-4-REV2-06/10	☑
HAND HELD MPG:		FANUC	☐	FUTURE(TAIWAN) ☐
		Sl. No.:		
TPM TRACK :		PIONEER CT	☐	☐
		Sl. No.:		
SERVO VOLTAGE STABILIZER:		15KVA	☐	25KVA ☐
INPUT:	OUTPUT:	MAKE: SERVOMAX	☐	☐
		Sl. No.:		
COOLANT / SPINDLE CHILLER UNIT:		MAKE: POINT	☐	☐
POWER:	MCB(F31):4A / 3P	Sl. No.:		
CONNECTOR :	INDO ELECTRIC (10 PIN) ☐	LOCATION: LHS	☐	RHS ☐

FIXTURE DETAIL

MAKE; Yuken	☑	PNEUMATIC ☐	HYDRAULIC ☑
STATION 1 CLAMP SOLENOID (Y70)	☑	STATION 1 DECLAMP SOLENOID (Y71)	☑
STATION 2 CLAMP SOLENOID (Y72)	☑	STATION 2 DECLAMP SOLENOID (Y73)	☑
STATION 3 CLAMP SOLENOID (Y84)	☑	STATION 3 DECLAMP SOLENOID (Y85)	☑
STATION 4 CLAMP SOLENOID (Y86)	☑	STATION 4 DECLAMP SOLENOID (Y87)	☑
MAKE; Polyhydron	☑	PNEUMATIC ☐	HYDRAULIC ☑
STATION 1 CLAMP PRESSURE SW (PRS20)	☑	STATION 2 CLAMP PRESSURE SW (PRS22)	☑
STATION 3 CLAMP PRESSURE SW (PRS31)	☑	STATION 4 CLAMP PRESSURE SW (PRS32)	☑

SPECIAL INFORMATIONS: CLAMP PB'S (GREEN) - 2 NOS.

DECLAMP PB'S (RED) - 1 NO.

CHECKED BY:- K.V.Kamath	VERIFIED BY:-

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

MACHINE HISTORY - ELECTRICAL

APC (LINEAR TYPE) DETAIL

NA

MANUAL OPERATION PANEL :	YSL-AMS-APC-PCB-REV0-07/06	☐
PALLET SET UP PB :	LUMINOUS GREEN	☐
EMERGENCY PB :	MUSHROOM HEAD RED	☐

PROXIMITY SENSORS:

MAKE; TEKNIC ☐ | TYPE: (24V DC - PNP) ☐

PALLET RECEIVED PROXIMITY(PXS11) ☐	M12X40	M12X52	M12X68	M12X73	
TYPE: CONNECTOR ☐ NON CONN. ☐	☐	☐	☐	☐	
ARM 1 IN PROXIMITY (PXS13) ☐	M12X40	M12X52	M12X68	M12X73	
TYPE: CONNECTOR ☐ NON CONN. ☐	☐	☐	☐	☐	
ARM 1 OUT PROXIMITY (PXS14) ☐	M12X40	M12X52	M12X68	M12X73	
TYPE: CONNECTOR ☐ NON CONN. ☐	☐	☐	☐	☐	
ARM 2 IN PROXIMITY (PXS15) ☐	M12X40	M12X52	M12X68	M12X73	
TYPE: CONNECTOR ☐ NON CONN. ☐	☐	☐	☐	☐	
ARM 2 OUT PROXIMITY (PXS16) ☐	M12X40	M12X52	M12X68	M12X73	
TYPE: CONNECTOR ☐ NON CONN. ☐	☐	☐	☐	☐	

PNEUMATIC SOLENOIDS:

NA

MAKE; FESTO ☐	TYPE: 24V DC -COIL ☐
APC DOOR OPEN SOLENOID (Y12) ☐	APC DOOR CLOSE SOLENOID (Y13) ☐
ALLET PAD CLEAN SOLENOID (Y18) ☐	☐

HYDRAULIC SOLENOIDS:

MAKE; YUKEN ☐ REXROTH ☐	TYPE: 24V DC -COIL ☐
PALLET CLAMP SOLENOID (Y10) ☐	PALLET DECLAMP SOLENOID (Y11) ☐
ARM 1 IN SOLENOID (Y14) ☐	ARM 1 OUT SOLENOID (Y15) ☐
ARM 2 IN SOLENOID (Y16) ☐	ARM 2 OUT SOLENOID (Y17) ☐

HYDRAULIC PRESSURE SWITCHES:

MAKE; POLYHYDRON ☐	TYPE: ☐
PALLET CLAMP PRSW (PRS3) ☐	PALLET DECLAMP PRSW (PRS60) ☐

LIMIT SWITCHES:

NA

MAKE; TEKNIC(NG1VS 510) ☐	JAI BALAJI (JLSSPR) ☐
PALLET 1 ON STATION LIMIT SW (LS10) ☐	PALLET 2 ON STATION LIMIT SW (LS11) ☐

READ SWITCHES:

MAKE; FESTO ☐	APC DOOR INTERMEDIATE READ SW (RSW 65) ☐
APC DOOR OPEN READ SW (RSW 58) ☐	APC DOOR CLOSE READ SW (RSW 59) ☐

SPECIAL INFORMATIONS:

CHECKED BY:- K.V.Rao	VERIFIED BY:

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

CHECK LIST - ELECTRICAL

M/C NUMBER:- M11-805 | DATE:- 25/04/2012

I.AXES

SL.No	PARAMETERS	STATUS	REMARKS
1	Specifications of servo motors are as per work order	✓	
2	Axes strokes are as per work order. (P1320 onwards)	✓	
3	All servomotors are taking normal current while running	✓	
4	Check Motor ID & other parameters of axis motor (P2020)	✓	
5	Axis cables are routed properly with suitable clamps & ties	✓	
6	Cables are connected properly both at motor & drive end	✓	
7	Lubrication timers & signals are as required to the machine	✓	
8	Rapid rate & feed rate of axes are as per workorder (P1420/1428)	✓	

II.SPINDLE

SL.No	PARAMETERS	STATUS	REMARKS
1	Specifications of spindle motor /speed /power is as per work order	✓	
2	Speed locking parameters If any are perfectly set (P3735,3736,)	✓	
3	Power locking parameters If any are perfectly set (P4028,4029)	NA	
4	Rigid tap parameters are set (P4016#4,4044,4052,4085,5241,5261)	✓	
5	Spi. running is checked for direction, noise if any, low & high speed	✓	
6	Spindle motor fan rotation /mpcb rating is checked	✓	
7	Spindle orientation is perfectly set (Proximity signal, parameter)	✓	
8	Manual tool declamp in jog is checked in twin arm models	✓	
9	Switching of Contactors for required speed incase of star/delta motor	NA	
10	Check cable connections both at motor & drive end	✓	

III.ATC

SL.No	PARAMETERS	STATUS	REMARKS
1	Check for latest tool change program(**O9001**) of the machine	✓	
2	Check for macro of twin arm machines	✓	
3	Check for Magazine indexing in both directions	✓	
4	Auto tool change is checked both in jog & auto mode	✓	
5	Check for position sw parameters,maco& reference parametres	✓	
6	Proximity sw cables are properly connected with tags & routed neatly	✓	
7	Tool display is matching with atc position	✓	
8	Power OFF conditions - Message and retrievals are checked	✓	

IV.APC

SL.No	PARAMETERS	STATUS	REMARKS
1	Check for pallet change program(**O9003&100**) of the machine.		
2	APC is operating manually through mop & in auto through **M80**		
3	Proximity sw & limit sw signals are checked for condition during		
	different operation	NA	
4	Working of pallet setup sequence		
5	Interrupt conditions checked & initialization procedure is displayed		
6	Working of fixture interlock if any for pallet change is checked		
7	Cables are routed properly with suitable clamps & ties		
8	Check for position sw parameters,maco& reference parametres		

CHECKED BY:- K.V.Hardy | VERIFIED BY:-

ACE MANUFACTURING SYSTEMS LTD

CHECK LIST - ELECTRICAL

AMS
In Pursuit of Excellence

V.PNUEMATIC

SL.No	PARAMETERS	STATUS	REMARKS
1	All solenoids / pressure switches are working for specified condition	✓	
2	Messages related to pressure sw settingis appearing when disturbed	✓	
3	Suitable element tags & indicators are put	✓	
4	Cables / plugs are terminated & routed properly	✓	
5	FRL unit signals are functioning properly (check FRL counter)	✓	

VI.HYDRAULIC

SL.No	PARAMETERS	STATUS	REMARKS
1	All solenoids /pressure switches are working for specified conditions	✓	
2	Messages related to pressure sw settings appearing when disturbed	✓	
3	Hydraulic Motor / cooling fan direction is checked	✓	
4	Oil level ,clog, temperature sensors if any, are working	N/A	
5	Suitable element tags & indicators are put	✓	
6	Cables / plugs are terminated & routed properly	✓	

VII.COOLANT

SL.No	PARAMETERS	STATUS	REMARKS
1	All coolant motors are running in cw direction	✓	
2	Timers for running all coolant / conveyor motors is checked	✓	
3	Float sw signals are functioning properly	✓	
4	Flow sw,clog sw & air blast is functioning properly in case of cts m/c	N/A	
5	Door close condition for coolant 'on' is checked if it is a option	✓	
6	Chip/ screw conveyors are working properly in auto & manual mode	✓	
7	Limit sw / proximity sw signals are functioning properly	✓	
8	MPCB used and settings done is as per the requirement	✓	

VIII.ROTARY/ INDEX TABLES

SL.No	PARAMETERS	STATUS	REMARKS
1	Table is checked for commanded positions & shortest path	✓	
2	Related logic is checked for proper running at safe position	✓	
3	Feedback signals are functioning properly	✓	
4	Related displays are marching with table position	✓	
5	Cable/ hoses are routed properly at safe position	✓	

IX.PANEL

SL.No	PARAMETERS	STATUS	REMARKS
1	MCB's are proper rated & connected as per circuit diagram	✓	
2	Rated MPCB's are set & connected as per circuit diagram	✓	
3	Contactors' of required rating & connected as per circuit diagram	✓	
4	Transformers of required rating & connected as per circuit diagram	✓	
5	Relay boards of proper rating & connected as per circuit diagram	✓	
6	Cables of proper rating & properly crimped at connection end	✓	
7	Drive cooling fans are working normally	✓	
8	Panel cooler setting & working is checked	✓	
9	Proper identification stickers / tags are fixed for all elements	✓	

CHECKED BY:- K.V.Jadhav | VERIFIED BY:-

ACE MANUFACTURING SYSTEMS LTD

CHECK LIST - ELECTRICAL

AMS — In Pursuit of Excellence

10	Cabinet is fully checked for loose connections if any	✓	
11	PCB , drive, I/O module connectors are firmly fixed	✓	
12	Machine operating panel connections are checked and routed	✓	
13	Moisture free beadings for cabinet are properly fixed	✓	
14	Moisture free beadings for operating panel are properly fixed	✓	

X.GENERAL

SL.No	PARAMETERS	STATUS	REMARKS
1	Illuminations of work lamps & indication lamps are satisfactory	✓	
2	Emergency circuit & monitor is functioning properly	✓	
3	Connections inside pendent are checked	✓	
4	Protective covers for the elements are given if required	✓	
5	All channel covers are fixed with proper fasteners	✓	
6	Protective earth is connected for elements which requires earthing	✓	
7	Safety instructions & other standard stickers are fixed on cabinet	✓	
8	PMC timer values are checked as per data sheet	✓	
9	New design changes are incorporated in the machine	✓	

INTERNAL CHECKLIST POINTS

→ Tag sticker. ✓
→ Chiller conn. name plate.
→ TB1 marker sheets. ✓
→ Auto drain cable to be properly routed ✓
→ Seal check related tags & name plates.
→ All warning related tags & name plates. ✓
→ Keypad stickers for Spm. ✓
→ Hyd related tags.
→ Screws & washers for Nol & Prsw. ✓

→ Varistor to be put for NTLCPL PCB
→ Servo guide pending.

XI. PMC DATA

Instruction: Please note all D-bits which is enabled at the time of shipping .
Also give the details if it is used for special function

D0	7	6	5	(4)	3	2	(1)	(0)	**D13**	7	6	5	4	3	2	1	0
D1	7	6	5	4	3	2	1	0	**D14**	7	6	5	4	3	2	1	0
D2	7	6	5	4	3	2	1	0	**D15**	7	6	5	4	3	2	1	0
D3	7	6	5	4	3	2	1	0	**D16**	7	6	5	4	3	2	1	0
D4	7	6	(5)	4	3	2	1	0	**D17**	7	6	5	4	3	2	1	0
D5	7	6	5	4	3	2	1	0	**D18**	7	6	5	4	3	2	1	0
D6	(7)	6	(5)	4	(3)	2	(1)	(0)	**D19**	7	6	5	4	3	2	1	(0)
D7	7	6	5	4	(3)	2	1	0	**D20**	7	6	5	4	3	2	1	0
D8	7	6	(5)	4	3	(2)	1	(0)	**D21**	7	6	5	4	3	2	1	0
D9	7	6	5	4	3	2	1	(0)	**D22**	7	6	5	4	3	2	1	0
D10	7	6	5	4	3	2	1	0	**D23**	7	6	5	4	3	2	1	0
D11	7	6	5	4	(3)	2	(1)	(0)	**D24**	7	(6)	(5)	4	3	2	1	0
D12	7	6	5	4	3	2	1	0	**D25**	7	6	5	4	3	2	1	0
D																	
D																	

D110	00000000	1	1
D000	00000000	3	30

CHECKED BY:- K.V. Ramesh

VERIFIED BY:-

ACE MANUFACTURING SYSTEMS LTD

CHECK LIST - ELECTRICAL

AMS — In Pursuit of Excellence

XII.PROGRAM/ LOGIC VERSION

Instruction: Please ckeck for latest version before making entry.

Logic version No.:	Remarks:
TMA01-01-04-M01.	

Progrm version Nos.:

O9001	VER A2.2.0	O9010		
O9002	VER B2.2.01	O9011		
O9003		O9012		
		O9013	VER M1.A.00	

XIII.CNC PARAMETERS

Instruction: Please Set the following parameters at the time of shipping .
Also give the details if any special parameter has set

✓	1301#7 = 1 Over travel before move	
✓	3103#2 = 1 System alarm history display.	
✓	3106#4 = 1.Operation history enable.	
✓	3108#6 = 1 Spindle load meter	
✓	3111#7 = 0 (NPA) - Message display	
✓	3112#0 = 0 Graphics display enable	
✓	3112#2 = 1 Operator message history display	
✓	3112#3 = 1 Alarm description display in alarm history screen for external alarms	
✓	3112#5 = 0 Operator history enable	
✓	3117#1 = 1. Spindle position feedback display in dgn 445	
✓	3205#4 = 1 In the offset screen offset value CLEAR by soft key to be disabled.	
✓	3402#6 =1 (CLR)Set the parameter	
✓	1601#4 = 1 (RTO)Set the parameter	
✓	1722 = 10/10/10 Set for RTO percentage	
✓	1826 =(500,500,500) ,1827=(200,200,200)-check inposition width	
✓	6910 - 6965 -check position switches values for ATC and APC	
✓	8132:0=1, - TOOL LIFE Parameters	
✓	6800#0 ,6801#3 , 6801#7 ,6804#2,6805#4 =1-6810=100, 6811=6, 6844=10, 6845=0	
✓	1620 & 1621 Rapid time constant	

	Check the following with system:		'1'		'0'	
	No.of Ladder steps**	Dgn:1141 # 6	9000		5000	**N/A for 0 iMD
	4th axis option**	1279 # 4 OR 1148 # 7	Yes		No	**N/A for 0 iMD
	Macro executer option	Dgn:1236 # 1	Yes		No	

XIV.SHIPPING

Instruction: Please perform following activities before shipping .
Also give the details if any special activity is done

SL.No	PARAMETERS	REMARKS
1	Take the servo guide back up	
2	Check the various communication like RS232C,PCMCIA	
3	Edit title,& set time, date other original factory set values	
4	Take all programs back up &Lock 8000 & 9000 series programs (P3202)	
6	Take the back up of following :	
	a)CNC parameters b) Pitch error compensation c)PMC parameters	
	d) JD- Info f)M- info e) Ladder g) macro i)S-RAM data	
7	Make I/O channel '0' for RS232C communication	
8	Keep spares inside the cabinet if any (eg.;Fuse)	
9	Check relevant circuit diagram of latest edition	
10	Ensure all the elements are in good condition before shipping	
11	Compare CNC parametrers with standard data & store in backup file	

CHECKED BY:- K.V.Jan	VERIFIED BY:-

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

FINAL ASSEMBLY - INSPECTION REPORT (VMC / CMM) - MECHANICAL

MACHINE NUMBER:	MIL - 805	CUSTOMER :	SAKTHI AUTO COMPONENT

I. MOTOR MOUNTING BRACKET FACE OUT AND CONCENTRICITY FOR DIRECT DRIVE

	FACE OUT (Recommended ≤ 0.015 mm)	CONCENTRICITY (Recommended ≤ 0.010 mm)
		

S.No.	DESCRIPTION	RECOMMENDED	ACTUAL
1	SPINDLE CONNECTOR RADIAL RUN OUT	≤ 0.010 MM	
2	MOTOR CURRENT AT MAX. RPM	β3 < 15%, β6 / α6 & ABOVE <10%	
3	CTS ROD GUIDE RADIAL RUN OUT (DDCTS)	≤ 0.010 MM	NA
4	SPINDLE CLAMPING FORCE	AS PER DS-DSN-PROD-01	
5	SPINDLE MOTOR SPECIFICATION	AS PER WORK ORDER	
II	INDIRECT DRIVE		
1	MOTOR PULLEY RADIAL RUN OUT	≤ 0.050MM	0-030 mm
2	SPINDLE PULLEY RADIAL RUN OUT	≤ 0.050MM	0-060 mm
3 a)	BELT TENSION	AS PER DS-DSN-PROD-02	✓
b)	BELT SPECIFICATION	Make : Size : - 770	Quantity : 01
4	MOTOR CURRENT AT MAX. RPM	β3 < 20%, β6 / α6 & ABOVE <15%	14 %
5	ROTARY JOINT RADIAL RUN OUT (IDCTS)	≤ 0.040MM	NA
6	SPINDLE CLAMPING FORCE -	AS PER DS-DSN-PROD-01	840 KG
7	SPINDLE MOTOR SPECIFICATION	AS PER WORK ORDER	B6 6000 RPM
8	PULLEY RATIO	AS PER WORK ORDER	1 : 1.5
III	AXIS DEAD STOPPER VALUE / BUTT REFERENCING VALUE (AS PER DRAWING)		
	AXIS	MOTOR END	BRAKE END
1	X	20.719	26.311
2	Y	~~20.000~~ 14.505	17.086
3	Z	6.450	26.250
IV	% of axis current drawn (Recommended as per Data sheet DS -QA -02)		
	AXIS	100 % rapid rate	
	X	46 %	
	Y	49 %	
	Z Down	28 %	
	Z Up	64 %	
V	ACCUMULATOR OIL PRESSURE	AS PER CIRCUIT DIAGRAM	NA
	ACCUMULATOR GAS PRESSURE	AS PER CIRCUIT DIAGRAM	NA
NAME & SIGN	Sreedharan CHECKED BY	APPROVED BY	1...6 PAGE NO

ACE MANUFACTURING SYSTEMS LTD

FINAL ASSEMBLY - INSPECTION REPORT (VMC / CMV) - MECHANICAL

AMS — Inv. Pursuit of Excellence

S.No.	DESCRIPTION	RECOMMENDED	ACTUAL
VI	ATC ALIGNMENT (TURRET TYPE)		
1	Parallelism-of gripper Arm face wrto. X - Axis	0.050 MM MAX.	
2	Tool Ejection Stroke	AS PER DS - DSN-PROD-01	
3	Swing Lever Gap	AS PER DRAWING	
4	Side Cam Alignment	0.020 MM MAX.	
5	Gap between Draw Bar bush & Roller/Screw	1 ± 0.1 MM	
VII	ATC ALIGNMENT (TWIN ARM)		
1	X - Axis	0.2 MM MAX.	0.1mm
2	Y - Axis	0.2 MM MAX.	0.090 mm
3	Z - Axis	0.050 MM MAX.	0.020 mm
4	Twin Arm bottom surface parallelism in Y-Axis	0.1MM MAX.	0.1 mm
5	Gap between Draw Bar Bush & Roller	1 ± 0.1 MM	1 mm
6	Tool Ejection stroke	AS PER DS - DSN-PROD-01	0.7 mm
7	Gap between deflection Pads	0.02 TO 0.050 MM	- NA -
VIII	APC ALIGNMENT - LINEAR TYPE		
1	Height difference of rest pads	0.010 MM MAX.	- NA -
2	Pallet change Time	AS PER WORK ORDER	- NA -
IX	APC ALIGNMENT- ROTARY TYPE		
1	APC Base parallelism w.r.to. X - Axis	≤ 0.1 MM	
	APC Base parallelism w.r.to. Y - Axis	≤ 0.1 MM	
2	Arm Top parallelism w.r.to. X - Axis	≤ 0.05 MM	
	Arm Top parallelism w.r.to. Y - Axis	≤ 0.05 MM	
3	Arm 1 Alignment ' FACE ' w.r.to X- Axis	≤ 0.020 MM	
	Arm 1 Alignment ' Taper ' w.r.to X - Axis	≤ 0.020 MM	
	Arm 2 Alignment ' FACE ' w.r.to X - Axis	≤ 0.020 MM	
	Arm 2 Alignment ' Taper ' w.r.to X - Axis	≤ 0.020 MM	
NAME & SIGN	CHECKED BY	APPROVED BY	PAGE NO 2...6

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

FINAL ASSEMBLY - INSPECTION REPORT (VMC / CMV) - MECHANICAL

S.No.	DESCRIPTION	RECOMMENDED	ACTUAL
4	Offset between Arm 1 & Arm 2 - Face	≤ 0.030 MM	
	Offset between Arm 1 & Arm 2 - Taper	≤ 0.030 MM	
5	Pallet - 1 Wedge Alignment along X - Axis	≤ 0.020 MM	
	Pallet - 2 Wedge Alignment along X - Axis	≤ 0.020 MM	
6	Gap between Pallet -1 side & Arm along X - Axis	Min 0.3 MM	
	Gap between Pallet -1 side & Arm along Z - Axis	0.1 ± 0.02 MM	
	Gap between Pallet -2 side & Arm along X - Axis	Min 0.3 MM	
	Gap between Pallet -2 side & Arm along Z - Axis	0.1 ± 0.02 MM	
7	Pallet Sagging - Pallet -1 'W.r.to. X & Y - Axis	≤ 1 MM	
	Pallet Sagging - Pallet -2 'W.r.to. X & Y - Axis	≤ 1 MM	
8	Pallet Height Variation	AS PER TEST CHART	
9	Backlash between Rack & Pinion at distance of 500 MM	≤ 1 MM	
10	Pallet Change Time	AS PER WORK ORDER	

S.No.	CHECK POINTS	REMARKS
A	**AXIS**	
1	Ensure geometrical accuracies as per test chart.	✓
2	Ensure plugs are fitted for LM guide ways.	✓
3	Ensure butt reference function.	✓
4	Ensure effective wiping of saddle cover wipers.	N/A
5	Ensure lube timer is set 12 min for HG and 20 min for LM Guide ways.	✓
6	Ensure leveling bolt locknuts are tighten after machine leveling.	✓
7	Check the all axes reference arrows are matched & Direction name plate fixed.	✓
8	Ensure tightness & marking of all screws with Yellow paint marker	✓
9	Ensure proper setting of Limit switches.	✓
B	**ATC**	
1	Check oil level is maximum in ATC gear box.	✓
2	Check tool change position limit switch for proper functioning & band width (Max. 1 mm on each side).	✓
3	Ensure smooth function of Tool change without abnormal/unhealthy noise.	✓
4	Ensure ATC bracket & Magazine Dowelling.	✓

NAME & SIGN			
	Sreedhesa CHECKED BY	APPROVED BY	3...6 PAGE NO

ACE MANUFACTURING SYSTEMS LTD		AMS
FINAL ASSEMBLY-INSPECTION REPORT (VMC / CMV) - MECHANICAL		In Pursuit of Excellence
S.No.	CHECK POINTS	REMARKS
C	SPINDLE	
1	Check the tightness of push stud.	✓
2	Ensure air jet through all the (4 / 8) holes at oriented spindle position	✓
3	Ensure supply of air to spindle Air Purge system (If provided)	NA
4	Ensure proper setting of proximities.	✓
5	Ensure smooth running of spindle without abnormal / unhealthy noise	✓
6	Ensure dummy plate fixing on CTS slot in Non CTS machine.	NA
7	Check the Tool not in spindle proximity message.	✓
D	COOLANT	
1	Ensure no coolant leakage around the machine & presence of coolant in lubrication oil drain pipe	✓
2	Ensure proper working of float switch (by shifting the sensor upwards).	✓
3	Ensure all the hoses, fittings tightened and routed properly.	✓
4	Check the function of Flood coolant (M7), Chip push (M181), Base flush (M182), CTS (M52) & Coolant gun (through selector switch).	✓
5	Ensure CTS flow sw.setting by opening the bag filter air vent ball valve.(Optional)	NA
6	Ensure suction strainer & Check Valve in CTS tank & pressure gauge working (If provided)	NA
7	Ensure CTS pin locator hole is plugged (If provided)	NA
8	Ensure that twin arm plunger & CTS pin locator screw do not foul (if provided)	NA
9	Ensure bag filter clog message by closing bag filter outlet ball valve (Optional)	NA
10	Ensure High pressure air blast after CTS switched off (If provided)	NA
11	Ensure drum wash in conveyors (If provided)	NA
12	Check conveyor overload message & Direction (If provided)	✓
13	Check oil in conveyor gear box. (if provided)	✓
14	Ensure functioning of screw conveyor in forward & reverse directions (through selector switch).	✓
15	Ensure splash guard fixed to conveyor.	✓
E	APC	
1	Ensure proper setting of proximities.	
2	Ensure supply of air jet to pallet rest pad cleaning.	
3	Ensure pallet change takes place smoothly with specified load (as per work order) without abnormal / unhealthy noise	NA
4	Ensure APC base Dowelling.	
5	Check pallet initialization in APC Machine	
NAME & SIGN	CHECKED BY: Preethaveer — APPROVED BY	4...6 Page No

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

FINAL ASSEMBLY -INSPECTION REPORT (VMC / CMV)- MECHANICAL

S.No.	CHECK POINTS	
F	**HYDRAULIC, PNEUMATIC & LUBRICATION**	
1	Ensure pneumatic main line pressure switch setting (4 bar) & error message are satisfactory	✓
2	Ensure Spindle air jet pressure switch setting (3 bar) & error message are satisfactory	✓
3	Ensure Spindle air purge pressure switch setting (1.2 bar) & error message are satisfactory	NA
4	Ensure proper setting of oil flow (1 drop/tool change) in FRL unit. & Oil Level low message	✓
5	Ensure proper routing of FRL drain hose.	✓
6	Ensure identification name plates are fixed on power pack hoses.	NA
7	Ensure Ball valve fixed to FRL Unit inlet	✓
8	Ensure pneumatic quick change coupling fixed to 4th axis provision	NA
9	Ensure no oil leakage in hydraulic valves & fittings	NA
10	Ensure hydraulic flow control valve grub locking in APC machine.	NA
11	Ensure pneumatic counter balance bracket Dowelling..	NA
G	**GUARDING ASSEMBLY**	
1	Ensure all internal guards are assembled.	✓
2	Ensure smooth movement of sliding door without play and unhealthy noise	✓
3	Ensure Nylock nuts are fixed to door rollers.	✓
4	Ensure ATC door LM rail plugs fixed.	NA
5	Ensure Proper tuning of Front auto door / ATC auto door cylinder.	✓
H	**ANY OTHER POINTS**	
1	Conveyer magnatic	✓
2	Bare guard	✓
3	Conveyor Top work	✓
4	Chip bin	✓
NAME & SIGN	CHECKED BY APPROVED BY	5...6 Page No.

CONTROLLED COPY

Sign: Date: 21/3/12

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

DESIGN VERIFICATION / VALIDATION PLAN CHART

TITLE: GEOMETRICAL ACCURACY TEST CHART FOR VERTICAL MACHINIG CENTER

All measurements in mm

SL. NO.	Description of the test	Figure	Tolerance	
			Permissible	Actual
G1	LEVELLING OF MACHINE X & Y AXES AT THEIR MIDDLE OF STROKE		0.03 / m ALONG X & Y AXES	LEVEL ALONG X-AXIS : 0.015 LEVEL ALONG Y-AXIS : 0.010
G2	PARALLELISM OF TABLE / PALLET SURFACE WITH RESPECT TO X-AXIS MOVEMENT		L ≤ 400 = 0.015 400 < L ≤ 630 = 0.025 630 < L ≤ 1000 = 0.040 1000 < L ≤ 2000 = 0.060 L= MOVEMENT OF THE TABLE / PALLET	TABLE : 0.006 PALLET 1 : PALLET 2 : (FOR APC MACHINE ONLY)
G3	PARALLELISM OF TABLE / PALLET SURFACE WITH RESPECT TO Y-AXIS MOVEMENT		L ≤ 400 = 0.015 400 < L ≤ 630 = 0.025 630 < L ≤ 1000 = 0.040 1000 < L ≤ 2000 = 0.060 L= MOVEMENT OF THE TABLE / PALLET	TABLE : 0.009 PALLET 1 : PALLET 2 : (FOR APC MACHINE ONLY)
G4	PARALLELISM OF REFERENCE T-SLOT TO X-AXIS MOVEMENT		L ≤ 400 = 0.015 400 < L ≤ 630 = 0.025 630 < L ≤ 1000 = 0.040 1000 < L ≤ 2000 = 0.060 L= MOVEMENT OF THE TABLE / PALLET	TABLE : 0.006 PALLET 1 : PALLET 2 : (FOR APC MACHINE ONLY)

CONTROLLED COPY

Sign: Date: 21/3/12

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

DESIGN VERIFICATION / VALIDATION PLAN CHART

TITLE: GEOMETRICAL ACCURACY TEST CHART FOR VERTICAL MACHINIG CENTER

All measurements in mm

SL. NO.	Description of the test	Figure	Tolerance	
			Permissible	Actual
G5	SQUARENESS OF SPINDLE AXIS TO TABLE SURFACE IN XZ PLANE. X & Y AXES AT THEIR MID STROKE		0.020 FOR 300mm SWING DIAMETER	TABLE : 0.008 PALLET 1 : PALLET 2 : (FOR APC MACHINE ONLY)
G6	SQUARENESS OF SPINDLE AXIS TO TABLE SURFACE IN YZ PLANE. X & Y AXES AT THEIR MID STROKE		0.020 FOR 300mm SWING DIAMETER	TABLE : 0.012 PALLET 1 : PALLET 2 : (FOR APC MACHINE ONLY)
G7	RUN OUT OF SPINDLE TAPER a) NEAR SPINDLE NOSE b) AT A DISTANCE OF 300 FROM SPINDLE NOSE		a. 0.01 NEAR SPINDLE NOSE b. 0.02 AT A DISTANCE OF 300mm	a. 0.002 b. 0.007
G8	PARALLELISM OF SPINDLE AXIS & Z-AXIS IN a) XZ PLANE b) YZ PLANE TO BE CHECKED AT MEAN POINT OF RUNOUT		a. 0.02 / 300 b. 0.02 / 300	a. 0.008 b. 0.010

CONTROLLED COPY

Sign: Date: 21/3/12

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

DESIGN VERIFICATION / VALIDATION PLAN CHART

TITLE: GEOMETRICAL ACCURACY TEST CHART FOR VERTICAL MACHINIG CENTER

SL. NO.	Description of the test	Figure	All measurements in mm Tolerance: Permissible	Actual
G9	SQUARENESS BETWEEN TABLE SURFACE & Z-AXIS MOVEMENT IN YZ PLANE		0.015 / 300	TABLE : 0.010 PALLET 1 : PALLET 2 : (FOR APC MACHINE ONLY)
G10	SQUARENESS BETWEEN TABLE SURFACE & Z-AXIS MOVEMENT IN XZ PLANE		0.015 / 300	TABLE : 0.011 PALLET 1 : PALLET 2 : (FOR APC MACHINE ONLY)
G11	STRAIGHTNESS OF X-AXIS MOVEMENT IN XY - PLANE		0.010 / 300	0.002
G12	STRAIGHTNESS OF Y-AXIS MOVEMENT IN XY - PLANE		0.010 / 300	0.003

SIGN & DATE	BSR	IG	RP	07-02-2012	4 OF 5	DS-DSN-TC-PROD-01-R3
	PREPARED	CHECKED	APPROVED	ISSUE DATE	PAGE No.	DOCUMENT No.

CONTROLLED COPY

Sign: Date: 21/3/12

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

DESIGN VERIFICATION / VALIDATION PLAN CHART

TITLE: GEOMETRICAL ACCURACY TEST CHART FOR VERTICAL MACHINIG CENTER

SL. NO.	Description of the test	Figure	All measurements in mm Tolerance: Permissible	Actual
G13	SQUARENESS OF Y - AXIS MOVEMENT WITH RESPECT TO X - AXIS MOVEMENT	MEASURE READING ALONG 'Y' ← → 	0.015 / 300	0.009
G14	VARIATION BETWEEN THE PALLET HEIGHT (FOR APC MACHINE ONLY)		0.030	N.A
G15	PALLET REPEATABILITY IN X & Y AXES WHEN LOADED ON THE MACHINE FROM THE PALLET STATION FOR SAME PALLET (FOR APC MACHINE ONLY)		0.020 IN X & Y AXES DIRECTION	PALLET 1 : N.A PALLET 2 : N.A (FOR APC MACHINE ONLY)

SIGN & DATE	BSR	IG	RP	07-02-2012	5 OF 5	DS-DSN-TC-PROD-01-R3
	PREPARED	CHECKED	APPROVED	ISSUE DATE	PAGE No.	DOCUMENT No.

ACE MANUFACTURING SYSTEMS LTD.

STANDARD TEST REPORT

1) HEAVY CUT REPORT :

MODEL	: MCV-400	BASE SPEED OF MOTOR	:1500	rpm	MATERIAL	: C.I.(Gr 25)
M/C NO.	: M11-805	SPINDLE SPEED RANGE	:60-6000	rpm	CUTTER	: Ø80 Sq.Sh FMC
TYPE OF MOTOR	: βi6/10000	MOTOR SPEED RANGE	:90-9000	rpm	WIDTH OF CUT	: 55 mm
PULLEY RATIO	: 1:1.5	MOTOR CAPACITY	:7.5/5.5	kW	C.S. (V)	: 250 mtr/min.

Spindle speed in rpm	Feed rate mm/ins.	Feed rate mm/rev.	Feed rate mm/min.	Depth Of Cut in mm	M R R cc/min.	'X' Axis % as per CRT	Spl.load % as per CRT	Remarks
1000	0.15	1.05	1050	2.0	116	28	45	SMOOTH CUTTING
1000	0.15	1.05	1050	3.9	225	38	89	SMOOTH CUTTING

RIGID TAPPING : M8×1.25 RIGID TAPPING TEST CONDUCTED, CHECKED WITH GAUGE & FOUND OK.

2) NAS TEST REPORT :

No.	Description of Test	Test Applied to	Permissible deviation	Actual Readings in mm
1	Flatness of Surface	A	0.015	0.006
2	Parallelism of Surfaces	N-L	0.020	0.004
		M-K	0.020	0.006
		H-F	0.030	0.004
		G-E	0.030	0.009
3	Squareness of side faces	K-L	0.020	0.011
		L-M	0.020	0.005
		M-N	0.020	0.006
		N-K	0.020	0.009
		E-F	0.030	0.006
		F-G	0.030	0.004
		G-H	0.030	0.007
		H-E	0.030	0.004
4	Circularity of Machining	J	0.040	0.013
5	Linear pitch in ' X ' axis	B1-B3 (100)	0.025	0.004
	Linear pitch in ' Y ' axis	B2-B4 (100)	0.025	0.002
	Diagonal pitch	C(70.71)	0.035	0.006
	Bore size variation		0.020	
	Hole No.	Max.	Min.	Ovality
	B1=	30.863	30.860	0.003
	B2=	30.865	30.861	0.004
	B3=	30.865	30.862	0.003
	B4=	30.864	30.860	0.004
7	Straightness	K	0.010	0.002
		L	0.010	0.006
		M	0.010	0.004
		N	0.010	0.004
		E	0.015	0.002
		F	0.015	0.003
		G	0.015	0.006
		H	0.015	0.002
8	Step difference in axis change over		0.010	0.002



SINGLE AXIS CONTROL K=L=M=N = 240 mm

DOUBLE AXIS CONTROL E=F=G=H = 160 mm

CIRCLE " J " = Ø231.50mm

Heavy cut Done By	NAS TEST DONE BY	Department incharge	QC / CMM
madan.P			
MADAN.P	RAJASHEKAR.K.P		
Date: 17/4/2012	DATE:27/4/2012	Date: 03/05/12	Date: 3/5/12

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

SPINDLE BALANCING REPORT

Machine Number : M/I-805

Spindle Serial Number : 10727

Spindle Type : BT 50

Spindle Speed (Max.) : 6000 rpm

Note : Refer TM-QA-09 for measurement procedure.



Location of balancing screw(s)

Sl No.	Speed in RPM	Velocity of vibration (mm/sec) before Balancing Along X-axis	After Balancing along X-axis (8000 rpm : 0.8 mm/sec max. > 8000 rpm : 1 mm/sec max.)	After Balancing along Y-axis (8000 rpm : 0.8 mm/sec max. > 8000 rpm : 1 mm/sec max.)
1	500			
2	1000	0.016	0.003	0.006
3	1500	0.027	0.009	
4	2000	0.005	0.010	0.005
5	2500	0.054	0.022	
6	3000	0.200	0.091	0.015
7	3500	0.334	0.098	
8	4000	0.112	0.058	0.031
9	4500	0.637 – 301°	0.117	
10	5000	0.915 – 288°	0.075	0.130
11	5500	1.15 – 270°	0.211	
12	6000	1.27 – 247°	0.156	0.068
13	6500			
14	7000			
15	7500			
16	8000			
17	8500			
18	9000			
19	9500			
20	10000			
21	10500			
22	11000			
23	11500			
24	12000			
25	12500			
26	13000			
27	13500			
28	14000			
29	14500			
30	15000			

Spindle maximum vibration mm / sec :

Correction in gms :

REMARK IF ANY: Added the mass on top portion M8X12 – 1

Date: 17/04/12

Checked By

APPROVED BY

ACE MANUFACTURING SYSTEMS LTD

SPINDLE ASSEMBLY - INSPECTION REPORT

AMS — In Pursuit of Excellence

Machine Number : M11-805	Spindle Unit Number: 10798
Spindle Drive ID / ID -CTS / DD / DD -CTS.	Max. Spindle Speed : 6000 RPM
Pull stud type DIN / MAS	Draw bar Type ID / ID-CTS / DD / DD-CTS
Bearing Make & Specification : SKF / BEAM ETPUS-UL	Draw bar SL No : 3179
Spindle Number: CH-578	Cartridge Number: 855

Spindle Nose Taper ISO-30 / 40 / 50 / HSK50 / 63 / 100

SL No.	Description	Recommended	Actual
1	Locknut Tightening Torque	Ref.DS-PDN-MEC-SA-08	115Nm
2	Spindle Bearing Preload	Ref.DS-PDN-MEC-SA-07	-0.008mm
3	Spindle Runout on taper	0.002 mm (*)	0.002mm
4	Mandrel Runout near the spindle nose	0.005 mm (*)	0.002mm
5	Mandrel Runout at 4 positions @ 90° at a distance of 300 mm (ISO 40/50, HSK 63), 250 mm (ISO 30, HSK 50) from spindle nose	10 micron (*)	1. 5 2. 4 3. 6 4. 5
6	Spindle stabilization temperature on Test rig	Upto 15° C above ambient	21°C - 33°C = 11°C
7	Check for abnormal / unhealthy noise	Abnormal / unhealthy noise not acceptable	OK
8	Pulley ratio (For ID machines)	Refer Work order	1:1.5 ratio
9	Number of Teeth on spindle pulley (For ID machines)	Ref.DS-DSN-PROD-02	81 / 54
10	Spindle pulley Runout (For ID machines)	0.050 mm (*)	0.050 mm
11	Spindle connector Runout (For DD machines)	0.010 mm (*)	—
12	Disc spring specification (Single / double stack)	Ref.DS-DSN-PROD-01	Alloy 90.8Y 3mm
13	Number of disc springs used	Ref.DS-DSN-PROD-01	66 nos
14	Disc spring Compression, Free length & Compressed length	Ref.DS-DSN-PROD-01	97.0 - 85.0 = 90mm
15	Tool clamping force	Ref.DS-DSN-PROD-01	Flow cap
16	ID-CTS Deublin Runout in Assembly condition (For CTS Spindle)	0.030 mm	Deublin Sl. No. : ..... Run out : .....

(*) To be measured after temperature stabilisation of spindle at max. speed.

REMARK IF ANY:

TEST ID:- 30032012 - 0108

Date: 19/03/12	Checked By	Approved By

10 18

10

3

8

0

6

0

ACE MANUFACTURING SYSTEMS LTD

HYDRAULIC ASSEMBLY - INSPECTION REPORT

AMS — In Pursuit of Excellence

MACHINE NUMBER : M11-805 SHAKTHI AUTO 24 STN 50 BOX PP

I. Power Pack Details			II. Pump Details	
1	Make :	Pascal / Hyd Tech / Rexorth / Yuken / ~~Jai Chamundi~~	Pump Make :	Rexroth / yuken /Corotech / vickers
2	Sl No. :	JCT-003-2012	Pump Sl. No. :	MFG NO: 1212
3	Tank capacity :	32 / 40 / ~~63~~ 70 Liters	Motor Make :	~~Rotomotive~~ / Siemens
4	Cooler make :	Pascal System Technik Pvt Ltd	Motor Sl. No :	N° M03122739
5	Cooler fan make :	EBM NADI	-	-
6	No.of stations :	1 / 2 / 3 / ~~4~~ 5 / 6	-	-

III	CHECK POINTS	Remark
1	Ensure Power pack is assembled as per circuit diagram & same is attached to inspection report.	✓
2	Ensure Accessories like Minnimess coupling, Guages are assembled.	✓
3	Ensure instruction name plates, power pack details, name plate are fitted	✓
4	All ports are tied with identification plate.	✓
5	Ensure there is no visual damage to the elements.	✓
6	Ensure oil level (at level indicator) in the hyd tank is at satisfactory	✓
7	Ensure tightness of all screws & marking neatly with yellow marker.	✓

IV	RUNNING CHECK POINTS	Remark
1	Check Motor direction is as per arrow marking.	✓
2	Ensure direction of rotation of cooler fan is as per arrow marking	✓
3	Ensure hydraulic pressure switch set as per circuit diagram.	✓
4	Ensure Accumulator oil & gas pressure as per circuit diagram (if applicable).	NA
5	Ensure no oil leakage from hydraulic system including at the oil level indicator & pipe joints	✓
6	Ensure continuous running of power pack for 4 hrs with solenoid actuation once per minute	✓
7	Power pack oil temp rise is within 30°C above ambient temp or 65 °C maximum.	✓
8	Check for any abnormal / unhealthy noise	✓

REMARK IF ANY: -

Date: 26/04/12	Checked by: Shashikumar.C	Approved by	

PRAGATI	AUTOMATIC TOOL CHANGER TEST REPORT		
SL NO: 15726	CUSTOMER I.D: 601-011-78	CUSTOMER: AMS	
PRODUCT I.D.: ATC1020V-084	PRODUCT DESCRIPTION: ATC 1020V-12.225-BT.DIN		
DESPATCH DATE: 16-03-2012			

TEST RESULTS:

TESTING HOURS	SPECIFIED: 6 Hrs.	ACTUAL: 6 Hours

PARAMETERS	SPECIFIED	ACTUAL		
		DURING ASSLY	AFTER 6 Hrs	DURING DESPATCH
ARM STROKE	114 -115mm	114.00	114.60	114.60
ARM AXIAL PLAY(IN PARKING)	0.20-1.50mm	1.00	1.20	1.20
ARM RADIAL PLAY @R250 IN PARKING	0.20-1.0mm	0.20	0.30	0.30
ARM RADIAL PLAY @R250 WHILE MOVING OUT	0.20-1.0mm	0.20	0.35	0.35
ARM RADIAL PLAY @R250 WHILE MOVING IN	0.20-1.0mm	0.30	0.50	0.50
ARM PARLLALITY	0-0.20mm	0.10	0.10	0.10
ARM PARK SIGNAL	Visual Check	OK	OK	OK
TOOL DECLAMP SIGNAL	Visual Check	OK	OK	OK
TOOL CLAMP SIGNAL	Visual Check	OK	OK	OK
BACKLASH OF WHEEL @R300	0.05-0.40mm	0.25	0.30	0.30
AXIAL PLAY OF WHEEL	0.01-0.10mm	0.06		

SENSING DISTANCE



PROXIMITY	SENSING GAP(S)	SENSOR LENGTH(L)
PS1	1.00	24.90
PS2	1.00	23.00
PS3	1.00	24.90
PS4	1.00	30.00
PS5	1.00	—
PS6	1.00	—
PS7	0.80	—

DESCRIPTION	NAME	SIGNATURE	DATE
ASSEMBLED BY	K.T.DHANANJAYA	K.T.Dhananjaya	14-03-12
CHECKED BY AFTER 6Hrs	Jagadeesh	Read	15/03/12
INSPECTED BY			
APPROVED BY	AKBER		17-03-12

PMI BALLSCREWS — BALLSCREW INSPECTION CERTIFICATE

Inspected By Agilent Laser Measuring System
All Measurement According To JIS B 1192: 1997



Specifications:	
·Customer	:AMS
·Order No.	:S3-110047983005
·Drawing No.	:BA300510003-0
·Part No.	: *: S12-016-97
·Specification	:R40-12C1-FDWE-796-1060-0.008
·Nominal Diameter (mm)	:40
·Nominal Pitch (mm)	:12
·Travel Length (mm)	:732
·E(μm)	:±18
·T(μm)	:-24

Measuring Result:	Permissible Error	Actual Measuring Error
·T+E(μm)	-42~-6	-19.99
·e(μm)	13	2.30
·e300(μm)	8	2.30
·Tq(kgf - cm)	4.16~7.28	4.16-5.2
·Accuracy Grade	C3	C0

Manufactured By
PRECISION MOTION IND., INC.
www.pmi-amt.com

Measuring Environment:
·Refernce Temperatrue : 20℃ ± 0.5℃
·Relative Humidity : 50% ± 10%
Measuring Device:
·Air Bearing guided Measuring Machine
·Agilent Laser Interferometer Type 5527A

QC
2011/11/23
PASS

Inspector: ARJAY

M11-895

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

BALL SCREW ASSEMBLY REPORT

Machine Number : M11-805	Ball screw Sl No: S3110047983005	Axis : Y

I. Ball screw Make & Specification : PMI [R40-1BC1-FDWG-796-1060-0.008].

II. Ball Screw Bearing Make & Specification : NACHI [25TAB06DB/GMP7].

Sl No	Description	Recommended	Motor End	Brake End
1	Ball screw rotational Torque (Forward / Reverse)	As per DS - PDN - MEC - SA - 02	1.7N/m	1.8N/M
2	Bearing housing Bore diameter	As per drawing	7to11	8to11
3	Bearing housing centre height difference	0.01 mm	0.01mm	—
4	Bearing housing bore parallelism with respect to pads	0.01 mm	0.005mm	0.005mm

Motor End

Sl No	Description	Part Number	Thickness (mm)	Depth / width
1	Flange cover (1) spigot depth	—	T1	—
2	Bearing width B1	—	T2	—
3	Bearing width B2	NACHI	T3	14.940
4	Bearing width B3	—" —	T4	14.945
5	Spacer cylindrical width B4	—	T5	—
6	Flange cover (2) spigot depth	C24-975-8193	T6	—
7	Housing Bearing depth	C37-103-8193	T7	43.505

IV. Flange cover thickness T6 = T7 - (T1+T2+T3+T4+T5)+0.05 mm 103|35

T6 = 13.680 mm

Brake End

Sl No	Description	Part Number	Thickness (mm)	Depth / width
1	Flange cover (1) spigot depth	—	T1	—
2	Bearing width B1	—	T2	—
3	Bearing width B2	NACHI	T3	14.940
4	Bearing width B3	—" —	T4	14.940
5	Spacer cylindrical width B4	—	T5	—
6	Flange cover (2) spigot depth	C24-360-8193	T6	—
7	Housing Bearing depth	C37-153-	T7	43.500

V. Flange cover thickness T6 = T7 - (T1+T2+T3+T4+T5)+0.05 mm 153|35

T6 = 13.680 mm

VI. Check points after assembly

	CHECK POINTS	Remark
1	Ensure the clearance between flange cover and bearing housing is 0.040 mm before tightening.	OK
2	Ensure Bearing housing flange concentricity is within 0.030 mm.	—" —
3	Ensure smooth rotation of ball screw assembly.	—" —
4	Ensure ball screw run out within 0.010 mm	—" —
5	Ensure tightness of all screws & marking with yellow marker	—" —
6	Ensure ball Screw report attached to Inspection Report	—" —

Date:	Checked by	Approved by

PMI BALLSCREW INSPECTION CERTIFICATE

Inspected By Agilent Laser Measuring System
All Measurement According To JIS B 1192: 1997



Specifications:	
·Customer	:AMS
·Order No.	:S3-110047981007
·Drawing No.	:BA300510002-0
·Part No.	:*:S12-016-95
·Specification	:R40-12C1-FDWE-846-1110-0.008
·Nominal Diameter (mm)	:40
·Nominal Pitch (mm)	:12
·Travel Length (mm)	:780
·E(μm)	:±18
·T(μm)	:-25

Measuring Result:	Permissible Error	Actual Measuring Error
·T+E(μm)	-43~-7	-35.80
·e(μm)	13	4.40
·e300(μm)	8	4.40
·Tq(kgf - cm)	4.16~7.28	4.16~5.2
·Accuracy Grade	C3	C2

Manufactured By
PRECISION MOTION IND., INC.
www.pmi-amt.com

Measuring Environment:
·Refernce Temperatrue : 20℃ ± 0.5℃
·Relative Humidity : 50% ± 10%
Measuring Device:
·Air Bearing guided Measuring Machine
·Agilent Laser Interferometer Type 5527A

QC
2011/12/02
PASS

Inspector: CAST

2011-985

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

BALL SCREW ASSEMBLY REPORT

Machine Number : MM-805	Ball screw Sl No: S31100 47981007	Axis : X

I. Ball screw Make & Specification : PMI FR40-12C1-FDWC-846-1110-0.008J

II. Ball Screw Bearing Make & Specification : NACHI 25TAB06DB/P4MJ

Sl No	Description	Recommended	Motor End	Brake End
1	Ball screw rotational Torque (Forward / Reverse)	As per DS - PDN - MEC - SA - 02	1.9 N/m	2.0 N/M
2	Bearing housing Bore diameter	As per drawing	11 to 12.11	11 to 11.10
3	Bearing housing centre height difference	0.01 mm	0.01 MM	
4	Bearing housing bore parallelism with respect to pads	0.01 mm	0.005 MM	0.005 MM

Motor End

Sl No	Description	Part Number	Thickness (mm)	Depth / width
1	Flange cover (1) spigot depth	—	T1	—
2	Bearing width B1	—	T2	—
3	Bearing width B2	NACHI	T3	14.950
4	Bearing width B3	— " —	T4	14.955
5	Spacer cylindrical width B4	—	T5	—
6	Flange cover (2) spigot depth	C24-375-8193	T6	—
7	Housing Bearing depth	C37-103-8193	T7	43.525

IV. Flange cover thickness T6 = T7 - (T1+T2+T3+T4+T5)+0.05 mm | 03 | 24

T6 = 13.680 mm

Brake End

Sl No	Description	Part Number	Thickness (mm)	Depth / width
1	Flange cover (1) spigot depth	—	T1	—
2	Bearing width B1	—	T2	—
3	Bearing width B2	NACHI	T3	14.950
4	Bearing width B3	— " —	T4	14.945
5	Spacer cylindrical width B4	—	T5	—
6	Flange cover (2) spigot depth	C24-360-8193	T6	—
7	Housing Bearing depth	C37-153-8193	T7	43.515

V. Flange cover thickness T6 = T7 - (T1+T2+T3+T4+T5)+0.05 mm | 153 | 24

T6 = 13.680 mm

VI. Check points after assembly

	CHECK POINTS	Remark
1	Ensure the clearance between flange cover and bearing housing is 0.040 min before tightening.	OK
2	Ensure Bearing housing flange concentricity is within 0.030 mm.	— " —
3	Ensure smooth rotation of ball screw assembly.	— " —
4	Ensure ball screw run out within 0.010 mm	— " —
5	Ensure tightness of all screws & marking with yellow marker	— " —
6	Ensure ball Screw report attached to Inspection Report	— " —

Date:	Checked by	Approved by

PMI BALLSCREWS — BALLSCREW INSPECTION CERTIFICATE

Inspected By Agilent Laser Measuring System
All Measurement According To JIS B 1192: 1997



Specifications:	
·Customer	:AMS
·Order No.	:S3-110047982013
·Drawing No.	:BA300510004-0
·Part No.	: *:S12-016-96
·Specification	:R40-12E1-FDWE-841-1105-0.008
·Nominal Diameter (mm)	:40
·Nominal Pitch (mm)	:12
·Travel Length (mm)	:780
·E(μm)	:±18
·T(μm)	:-25

Measuring Result:	Permissible Error	Actual Measuring Error
·T+E(μm)	-43～-7	-37.52
·e(μm)	13	4.55
·e300(μm)	8	4.55
·Tq(kgf - cm)	5.72～9.88	6.76-7.8
·Accuracy Grade	C3	C2

Manufactured By
PRECISION MOTION IND., INC.
www.pmi-amt.com

Measuring Environment:
·Refernce Temperatrue : 20℃ ± 0.5℃
·Relative Humidity : 50% ± 10%
Measuring Device:
·Air Bearing guided Measuring Machine
·Agilent Laser Interferometer Type 5527A

QC
2011/11/17
PASS

Inspector: Angus

ACE MANUFACTURING SYSTEMS LTD

AMS — In Pursuit of Excellence

BALL SCREW ASSEMBLY REPORT

Machine Number : M11-805 — | Ball screw Sl No: 331100479882 03 | Axis : Z

I . Ball screw Make & Specification : PMI [R40-12E1-FDWG-841-1105-0.008].

II. Ball Screw Bearing Make & Specification : NACHI [95TAB06DB/GMP4]

Sl No	Description	Recommended	Motor End	Brake End
1	Ball screw rotational Torque (Forward / Reverse)	As per DS - PDN :- MEC - SA - 02	1.8 N/m	1.9 N/m.
2	Bearing housing Bore diameter	As per drawing	6 to 4.11.	11 to 10.11
3	Bearing housing centre height difference	0.01 mm	—	—
4	Bearing housing bore parallelism with respect to pads	0.01 mm	—	0.005 mm

Motor End

Sl No	Description	Part Number	Thickness (mm)	Depth / width
1	Flange cover (1) spigot depth	C24-391-8183	T1	13.777
2	Bearing width B1	—	T2	—
3	Bearing width B2	NACHI	T3	14.954
4	Bearing width B3	— " —	T4	14.948
5	Spacer cylindrical width B4	—	T5	—
6	Flange cover (2) spigot depth	C24-391-8183	T6	—
7	Housing Bearing depth	C37-701-8183	T7	56.972.

IV. Flange cover thickness T6 = T7 - (T1+T2+T3+T4+T5)+0.05 mm 701/81 (7)

T6 = 13.380. mm

Brake End

Sl No	Description	Part Number	Thickness (mm)	Depth / width
1	Flange cover (1) spigot depth	—	T1	—
2	Bearing width B1	—	T2	—
3	Bearing width B2	NACHI	T3	14.930
4	Bearing width B3	— " —	T4	14.930
5	Spacer cylindrical width B4	—	T5	—
6	Flange cover (2) spigot depth	C24-380-8183	T6	—
7	Housing Bearing depth	C37-154-8183	T7	43.480

V. Flange cover thickness T6 = T7 - (T1+T2+T3+T4+T5)+0.05 mm 154/11

T6 = 13.70 mm

VI. Check points after assembly

	CHECK POINTS	Remark
1	Ensure the clearance between flange cover and bearing housing is 0.040 mm before tightening.	OK
2	Ensure Bearing housing flange concentricity is within 0.030 mm.	— " —
3	Ensure smooth rotation of ball screw assembly.	— " —
4	Ensure ball screw run out within 0.010 mm	— " —
5	Ensure tightness of all screws & marking with yellow marker	— " —
6	Ensure ball Screw report attached to Inspection Report.	— " —

Date: | Checked by | Approved by

ACE MANUFACTURING SYSTEM LTD.

Machine No :-	M11-805.	Date :-	2012-04-18 14:10
Machine Modle :-	MCV-400.	Cond by:-	QAS/RKU.

AXIS CALIBRATION PITCH ERROR REPORT

X				Y				Z			
SL NO 100 (X)	0			SLNO 200 (Y)	0			SL NO 300 (Z)	0		
101	0	141	0	201	2	241	1	301	0	341	1
102	0	142	0	202	1	242	0	302	1	342	0
103	0	143	0	203	0	243	1	303	1	343	0
104	0	144	0	204	0	244	0	304	0	344	1
105	0	145	0	205	0	245	4	305	0	345	1
106	1	146	0	206	-1	246		306	1	346	2
107	0	147	0	207	0	247		307	0	347	1
108	0	148	0	208	0	248		308	1	348	0
109	1	149	1	209	1	249		309	0	349	2
110	0	150	0	210	1	250		310	0	350	2
111	0	151	0	211	1	251		311	1	351	
112	1	152	0	212	0	252		312	0	352	
113	0	153	0	213	0	253		313	0	353	
114	0	154	0	214	0	254		314	0	354	
115	1	155	0	215	1	255		315	-1	355	
116	0	156	0	216	0	256		316	-1	356	
117	1	157	1	217	0	257		317	-1	357	
118	0	158	0	218	1	258		318	0	358	
119	0	159	1	219	0	259		319	0	359	
120	0	160	0	220	0	260		320	0	360	
121	0	161		221	-1	261		321	0	361	
122	0	162		222	0	262		322	-1	362	
123	0	163		223	0	263		323	0	363	
124	0	164		224	0	264		324	-1	364	
125	0	165		225	1	265		325	0	365	
126	0	166		226	0	266		326	0	366	
127	0	167		227	1	267		327	1	367	
128	0	168		228	0	268		328	1	368	
129	0	169		229	0	269		329	0	369	
130	0	170		230	-1	270		330	1	370	
131	0	171		231	0	271		331	0	371	
132	0	172		232	0	272		332	2	372	
133	0	173		233	1	273		333	2	373	
134	1	174		234	0	274		334	1	374	
135	0	175		235	0	275		335	0	375	
136	-1	176		236	0	276		336	1	376	
137	0	177		237	0	277		337	1	377	
138	0	178		238	0	278		338	2	378	
139	1	179		239	0	279		339	1	379	
140	0	180		240	0	280		340	0	380	

SL NO	PARAMETER NO	DISCRIPTION	X	Y	Z
1	3620	P COMP REF NO	160	245	350
2	3621	P COMP MIN NO	100	200	300
3	3622	P COMP MAX NO	165	250	355
4	3623	PCOMP MULTIPLICATION	10	10	10
5	3624	P COMP INTERVAL	10	10	10

ACE MANUFACTURING SYSTEM LTD.

AMS
In Pursuit of Excellence

M/c NO :- M11-805.	COND BY:- QAS/RKU.
Machine Modle :- MCV-400.	DATE:- 19-Apr-12

AXIS CALIBRATION BALL BAR PARAMETERS

SERVO PARAMETERS RELATED TO CIRCULARITY FOR FANUC SYSTEM

SL No.	PARAMETER No.	TYPICAL VALUE	DESCRIPTION	X	Y	Z	REMARKS
1	1851	###	BACKLASH IN FEED	35	85	35	
2	1852	###	BACKLASH IN RAPID	20	60	15	
3	1825	8000	SERVO LOOP GAIN	5000	5000	5000	
4	1826	500	IN POSITION WIDTH	500	500	500	
5	2021	256	LOAD INERTIA	192	128	161	*****
6	2048	600 (###)	BACK ACCEL COMPENSATION VALUE	35	-65	35	
7	2094	600 (###)	BACK ACCEL COMPENSATION VALUE	35	-65	35	
8	2066	10 TO -20	250 MICRO SEC ACC FEEDBACK	-10	-10	-10	*****
9	2068	70 TO700	FEED FWD CO- EFFICIENT	100	100	100	
10	2069	50 TO 200	VELOCITY FEED FWD CO- EFFICIENT FOR RAPID	100	100	100	
11	2071	50 TO 200	TIME DURING WHICH BACK ACCELERATION IS EFFECTIVE	100	100	100	
12	2145	100	VELOCITY FEED FWD CO- EFFICIENT FOR CUTTING	100	100	100	SHOULD NOT BE CHANGED
13	2144	9900	LOOK AHEAD FFW COEFFICIENT FOR CUTTING	9900	9900	9900	
14	2092	9200	LOOK AHEAD FFW COEFFICIENT FOR RAPID	9200	9200	9200	
15	2082	100	STAGE 2 START / END PARAMETER	100	100	100	
16	2039	100	STAGE 2 ACCELERATION AMOUNT	300	300	300	
17	1622	NA	CUT TIME CONSTANT	64	64	64	Same value for 3 axis

NOTE:-
***** DON'T CHANGE THE VALUE
VARIES FOR ALL MACHINES

Ballbar diagnostics table
M11-805-XY-C

Operator: Shivu.
Date: 2012-Apr-19 11:15:47

RENISHAW

Machine: QuickCheck
Instrument: QC10 ballbar

Error	Magnitude		Independent circularity		Ranking
Backlash X	▸0.0	◂0.0 µm	0.0 µm	(0%)	(13)
Backlash Y	▴-0.2	▾1.1 µm	1.1 µm	(6%)	(6)
Reversal spikes X	▸1.6	◂0.0 µm	1.6 µm	(9%)	(3)
Reversal spikes Y	▴0.5	▾-5.4 µm	5.4 µm	(31%)	(1)
Lateral play X	▸1.3	◂-1.3 µm	0.6 µm	(4%)	(9)
Lateral play Y	▴0.1	▾0.4 µm	0.3 µm	(2%)	(11)
Cyclic error X	↑0.7	↓0.6 µm	0.7 µm	(4%)	(8)
Cyclic error Y	↑1.3	↓1.3 µm	1.2 µm	(7%)	(4)
Servo mismatch	0.07 ms		1.1 µm	(6%)	(5)
Squareness	-25.2 µm/m		3.8 µm	(22%)	(2)
Straightness X	-0.6 µm		0.3 µm	(2%)	(12)
Straightness Y	-1.4 µm		0.7 µm	(4%)	(7)
Scaling mismatch	-0.9 µm		0.5 µm	(3%)	(10)
Cyclic pitch X	24.0000 mm				
Cyclic pitch Y	44.4500 mm				
Scaling error X	-0.5 ppm				
Scaling error Y	2.5 ppm				
Calculated feedrate	1000.8 mm/min				
Centre offset X	-0.3 µm				
Centre offset Y	0.7 µm				
Positional tolerance	16.2 µm				
Best fit radius	150.0002 mm				
Circularity	13.0 µm				

Test Parameters

Radius	150.0000mm
Feedrate	1000.0mm/min
Start/End/Overshoot	0°/360°/180°
Run sequence	CW CCW

ISO 230-4:1996(E) Circular Deviation
M11-805-XY-C

Operator: Shivu.
Date: 2012-Apr-19 11:15:47

RENISHAW

Machine: QuickCheck
Instrument: QC10 ballbar

Circular Deviation (CW)

Value	12.6µm

Test Parameters

Radius	150.0000mm
Sample rate	26.316Hz
Feedrate	1000.0mm/min
Run direction	CW
Plane under test	XY
Test position	
Start angle	0°
End angle	360°
Overshoot angle	180°



Run 1

10.0 µm/div

ISO 230-4:1996(E) Circular Deviation
M11-805-XY-C

Operator: Shivu.
Date: 2012-Apr-19 11:15:47

RENISHAW

Machine: QuickCheck
Instrument: QC10 ballbar

Circular Deviation (CCW)

Value	11.8µm

Test Parameters

Radius	150.0000mm
Sample rate	26.316Hz
Feedrate	1000.0mm/min
Run direction	CCW
Plane under test	XY
Test position	
Start angle	0°
End angle	360°
Overshoot angle	180°



Run 2

10.0 µm/div

Ballbar diagnostics table
M11-805-XZ-B

Operator: Shivu.
Date: 2012-Apr-19 11:36:10

RENISHAW

Machine: QuickCheck
Instrument: QC10 ballbar

Error	Magnitude		Independent circularity		Ranking
Backlash Z	▵-0.2	▿0.2 µm	0.2 µm	(1%)	(12)
Backlash X	‹-0.1	›0.2 µm	0.2 µm	(1%)	(11)
Reversal spikes Z	▵-1.9	▿-2.2 µm	2.2 µm	(7%)	(4)
Reversal spikes X	‹-0.2	›-1.8 µm	1.8 µm	(6%)	(5)
Lateral play Z	▵-1.4	▿0.2 µm	0.9 µm	(3%)	(10)
Lateral play X	‹0.1	›0.1 µm	0.1 µm	(0%)	(13)
Cyclic error Z	↑1.4	↓1.1 µm	1.2 µm	(4%)	(8)
Cyclic error X	↑1.5	↓1.3 µm	1.4 µm	(5%)	(6)
Servo mismatch	-0.07 ms		1.2 µm	(4%)	(9)
Squareness	-59.0 µm/m		8.8 µm	(29%)	(1)
Straightness Z	-2.5 µm		1.3 µm	(4%)	(7)
Straightness X	14.4 µm		7.2 µm	(23%)	(2)
Scaling mismatch	-8.4 µm		4.2 µm	(14%)	(3)
Cyclic pitch Z	50.0000 mm				
Cyclic pitch X	40.0000 mm				
Scaling error Z	20.7 ppm				
Scaling error X	48.8 ppm				
Calculated feedrate	1000.8 mm/min				
Centre offset Z	-1.1 µm				
Centre offset X	-2.9 µm				
Positional tolerance	56.0 µm				
Best fit radius	150.0052 mm				
Circularity	17.8 µm				

Test Parameters

Radius	150.0000mm
Feedrate	1000.0mm/min
Start/End/Overshoot	90°/90°/180°
Run sequence	CW CCW

ISO 230-4:1996(E) Circular Deviation
M11-805-XZ-B

Operator: Shivu.
Date: 2012-Apr-19 11:36:10

RENISHAW

Machine: QuickCheck
Instrument: QC10 ballbar

Circular Deviation (CW)

Value	17.7µm

Test Parameters

Radius	150.0000mm
Sample rate	26.316Hz
Feedrate	1000.0mm/min
Run direction	CW
Plane under test	ZX
Test position	
Start angle	90°
End angle	90°
Overshoot angle	180°



Run 1

10.0 µm/div

ISO 230-4:1996(E) Circular Deviation
M11-805-XZ-B

Operator: Shivu.
Date: 2012-Apr-19 11:36:10

RENISHAW

Machine: QuickCheck
Instrument: QC10 ballbar

Circular Deviation (CCW)

Value	17.2µm

Test Parameters

Radius	150.0000mm
Sample rate	26.316Hz
Feedrate	1000.0mm/min
Run direction	CCW
Plane under test	ZX
Test position	
Start angle	90°
End angle	90°
Overshoot angle	180°



Run 2

10.0 µm/div

Ballbar diagnostics table
M11-805-YZ-A

Operator: Shivu.
Date: 2012-Apr-19 11:55:00

RENISHAW

Machine: QuickCheck
Instrument: QC10 ballbar

Error	Magnitude		Independent circularity		Ranking
Backlash Y	▸-0.5	◂1.1 µm	1.1 µm	(4%)	(8)
Backlash Z	▲-0.9	▾-0.2 µm	0.9 µm	(4%)	(10)
Reversal spikes Y	▸-5.0	◂-5.3 µm	5.3 µm	(20%)	(2)
Reversal spikes Z	▲-0.2	▾-2.2 µm	2.2 µm	(8%)	(4)
Lateral play Y	▸-0.2	◂0.0 µm	0.1 µm	(0%)	(13)
Lateral play Z	▲1.9	▾-1.6 µm	1.0 µm	(4%)	(9)
Cyclic error Y	↑1.5	↓1.6 µm	1.5 µm	(6%)	(6)
Cyclic error Z	↑1.3	↓1.5 µm	1.4 µm	(5%)	(7)
Servo mismatch	-0.01 ms		0.2 µm	(1%)	(12)
Squareness	4.7 µm/m		0.7 µm	(3%)	(11)
Straightness Y	12.7 µm		6.4 µm	(24%)	(1)
Straightness Z	3.3 µm		1.7 µm	(6%)	(5)
Scaling mismatch	8.4 µm		4.2 µm	(16%)	(3)
Cyclic pitch Y	38.1000 mm				
Cyclic pitch Z	50.8000 mm				
Scaling error Y	49.6 ppm				
Scaling error Z	21.6 ppm				
Calculated feedrate	1000.4 mm/min				
Centre offset Y	0.8 µm				
Centre offset Z	10.5 µm				
Positional tolerance	42.3 µm				
Best fit radius	150.0053 mm				
Circularity	16.9 µm				

Test Parameters

Radius	150.0000mm
Feedrate	1000.0mm/min
Start/End/Overshoot	0°/360°/180°
Run sequence	CW CCW

ISO 230-4:1996(E) Circular Deviation
M11-805-YZ-A

Operator: Shivu.
Date: 2012-Apr-19 11:55:00

RENISHAW

Machine: QuickCheck
Instrument: QC10 ballbar

Circular Deviation (CW)

Value	14.2µm

Test Parameters

Radius	150.0000mm
Sample rate	26.316Hz
Feedrate	1000.0mm/min
Run direction	CW
Plane under test	YZ
Test position	
Start angle	0°
End angle	360°
Overshoot angle	180°



Run 1

10.0 µm/div

ISO 230-4:1996(E) Circular Deviation
M11-805-YZ-A

Operator: Shivu.
Date: 2012-Apr-19 11:55:00

RENISHAW

Machine: QuickCheck
Instrument: QC10 ballbar

Circular Deviation (CCW)

Value	17.2µm

Test Parameters

Radius	150.0000mm
Sample rate	26.316Hz
Feedrate	1000.0mm/min
Run direction	CCW
Plane under test	YZ
Test position	
Start angle	0°
End angle	360°
Overshoot angle	180°



Run 2

10.0 µm/div

RENISHAW CALIBRATION INTERFEROMETER SYSTEM

ENVIRONMENT DATA PRINT-OUT

Mode : Linear displacement

File: M11-805-X.RTL

Machine:MCV-400.
Date:2012-04-18 14:34
Axis:X.

Serial No:M11-805.
By:QAS/RKU.
Location:AMS.

TITLE:POSITIONING ACCURACY.

Data	Start	End	Units
Time :	2012-04-18 14:35	2012-04-18 14:56	
Air temperature :	31.22	31.30	deg C
Air pressure :	904.80	904.40	mbar
Rel. humidity :	49.68	48.75	%
Material Temperature 1 :	--NC--	--NC--	deg C
Material Temperature 2 :	30.83	30.88	deg C
Material Temperature 3 :	--NC--	--NC--	deg C
Exp. Coeff :	11.70	11.70	ppm/deg C
Environment factor :	0.31638154	0.31638139	

VDI 3441

POSITIONING ACCURACY.



VDI 3441 - Linear

Machine:MCV-400.	Axis:X.	U max : 1.000
Serial No:M11-805.	Location:AMS.	P : 4.283
Date:2012-04-18 14:34	U mean : 0.225	Ps max : 2.683
By:QAS/RKU.	Ps mean : 0.895	Pa : 1.800

RENISHAW CALIBRATION INTERFEROMETER SYSTEM
ALL DATA

Machine:MCV-400. Serial No:M11-805.
Date:2012-04-18 14:34 By:QAS/RKU.
Axis:X. Location:AMS.
TITLE:POSITIONING ACCURACY. Filename: M11-805-X.RTL

Units of data values are micrometres

Target 1 (+) (0.0000 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 1 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 2 (+) (39.9990 millimetres)
1) 1.0 2) 0.0 3) 1.0 4) 1.0
5) 1.0
Target 2 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 3 (+) (79.9980 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 3 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 4 (+) (119.9970 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 4 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 5 (+) (159.9960 millimetres)
1) -1.0 2) -1.0 3) 0.0 4) -1.0
5) -1.0
Target 5 (-)
1) -1.0 2) -1.0 3) -1.0 4) -1.0
5) 0.0

Target 6 (+) (199.9950 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 6 (-)
1) -1.0 2) -1.0 3) 0.0 4) -1.0
5) 0.0

Target 7 (+) (239.9940 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 7 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 8 (+) (279.9930 millimetres)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 8 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 9 (+) (319.9920 millimetres)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0
Target 9 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 10 (+) (359.9910 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 10 (-)
1) 0.0 2) 0.0 3) 1.0 4) 0.0
5) 1.0

Target 11 (+) (399.9900 millimetres)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 0.0
Target 11 (-)
1) 0.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 12 (+) (439.9890 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 12 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 13 (+) (479.9880 millimetres)
1) 0.0 2) -1.0 3) 0.0 4) 0.0
5) 0.0
Target 13 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 14 (+) (519.9870 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 1.0
5) 0.0
Target 14 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 15 (+) (559.9860 millimetres)
1) 1.0 2) 0.0 3) 1.0 4) 1.0
5) 0.0
Target 15 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 16 (+) (599.9850 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 16 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

RENISHAW CALIBRATION INTERFEROMETER SYSTEM

ENVIRONMENT DATA PRINT-OUT

Mode : Linear displacement

File: M11-805-Y.RTL

Machine:MCV-400.
Date:2012-04-18 15:54
Axis:Y.

Serial No:M11-805.
By:QAS/RKU.
Location:AMS.

TITLE:POSITIONING ACCURACY.

Data	Start	End	Units
Time :	2012-04-18 15:54	2012-04-18 16:03	
Air temperature :	31.47	30.95	deg C
Air pressure :	903.80	904.20	mbar
Rel. humidity :	45.21	49.54	%
Material Temperature 1 :	--NC--	--NC--	deg C
Material Temperature 2 :	30.98	30.96	deg C
Material Temperature 3 :	--NC--	--NC--	deg C
Exp. Coeff :	11.70	11.70	ppm/deg C
Environment factor :	0.31638108	0.31638102	

VDI 3441

POSITIONING ACCURACY.



VDI 3441 - Linear

Machine:MCV-400.	Axis:Y.	U max : 1.000
Serial No:M11-805.	Location:AMS.	P : 4.136
Date:2012-04-18 15:54	U mean : 0.350	Ps max : 3.286
By:QAS/RKU.	Ps mean : 1.595	Pa : 1.800

RENISHAW CALIBRATION INTERFEROMETER SYSTEM
ALL DATA

Machine:MCV-400. Serial No:M11-805.
Date:2012-04-18 15:54 By:QAS/RKU.
Axis:Y. Location:AMS.
TITLE:POSITIONING ACCURACY. Filename: M11-805-Y.RTL

Units of data values are micrometres

Target 1 (+) (0.0000 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 1 (-)
1) -1.0 2) -1.0 3) -1.0 4) -1.0
5) -1.0

Target 2 (+) (29.9990 millimetres)
1) 1.0 2) 1.0 3) 0.0 4) 0.0
5) 0.0
Target 2 (-)
1) 1.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 3 (+) (59.9980 millimetres)
1) 0.0 2) 0.0 3) -1.0 4) -1.0
5) -1.0
Target 3 (-)
1) -1.0 2) -1.0 3) -1.0 4) -1.0
5) -1.0

Target 4 (+) (89.9970 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) -1.0
5) -1.0
Target 4 (-)
1) 0.0 2) 0.0 3) -1.0 4) -1.0
5) -1.0

Target 5 (+) (119.9960 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) -1.0
Target 5 (-)
1) 0.0 2) 0.0 3) -1.0 4) -1.0
5) -1.0

Target 6 (+) (149.9950 millimetres)
1) 1.0 2) 1.0 3) 0.0 4) 0.0
5) 0.0
Target 6 (-)
1) 1.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 7 (+) (179.9940 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 7 (-)
1) 0.0 2) -1.0 3) -1.0 4) -1.0
5) -1.0

Target 8 (+) (209.9930 millimetres)
1) 1.0 2) 1.0 3) 1.0 4) 0.0
5) 0.0

Target 8 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 9 (+) (239.9920 millimetres)
1) 1.0 2) 1.0 3) 1.0 4) 0.0
5) 1.0
Target 9 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 10 (+) (269.9910 millimetres)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0
Target 10 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 11 (+) (299.9900 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 11 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 12 (+) (329.9890 millimetres)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0
Target 12 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 13 (+) (359.9880 millimetres)
1) 1.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 13 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 14 (+) (389.9870 millimetres)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0
Target 14 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 15 (+) (419.9860 millimetres)
1) 1.0 2) 1.0 3) 0.0 4) 0.0
5) 0.0
Target 15 (-)
1) 0.0 2) 0.0 3) 1.0 4) 0.0
5) 0.0

Target 16 (+) (449.9850 millimetres)
1) 1.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 16 (-)
1) 0.0 2) 0.0 3) -1.0 4) -1.0
5) -1.0

RENISHAW CALIBRATION INTERFEROMETER SYSTEM

ENVIRONMENT DATA PRINT-OUT

Mode : Linear displacement

File: M11-805-Z.RTL

Machine:MCV-400.
Date:2012-04-18 17:22
Axis:Z.

Serial No:M11-805.
By:QAS/RKU.
Location:AMS.

TITLE:POSITIONING ACCURACY.

Data	Start	End	Units
Time :	2012-04-18 17:23	2012-04-18 17:32	
Air temperature :	28.52	28.55	deg C
Air pressure :	904.40	904.60	mbar
Rel. humidity :	55.43	55.45	%
Material Temperature 1 :	--NC--	--NC--	deg C
Material Temperature 2 :	30.20	30.15	deg C
Material Temperature 3 :	--NC--	--NC--	deg C
Exp. Coeff :	11.70	11.70	ppm/deg C
Environment factor :	0.31638321	0.31638341	

VDI 3441

POSITIONING ACCURACY.



VDI 3441 - Linear

Machine:MCV-400.	Axis:Z.	U max : 0.800
Serial No:M11-805.	Location:AMS.	P : 3.492
Date:2012-04-18 17:22	U mean : 0.200	Ps max : 1.643
By:QAS/RKU.	Ps mean : 0.597	Pa : 2.000

RENISHAW CALIBRATION INTERFEROMETER SYSTEM
ALL DATA

Machine:MCV-400. Serial No:M11-805.
Date:2012-04-18 17:22 By:QAS/RKU.
Axis:Z. Location:AMS.
TITLE:POSITIONING ACCURACY. Filename: M11-805-Z.RTL

Units of data values are micrometres

Target 1 (+) (0.0000 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 1 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 2 (+) (33.3330 millimetres)
1) -1.0 2) -1.0 3) -1.0 4) -1.0
5) -1.0
Target 2 (-)
1) 0.0 2) 0.0 3) 0.0 4) -1.0
5) 0.0

Target 3 (+) (66.6660 millimetres)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0
Target 3 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

Target 4 (+) (99.9990 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 4 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 5 (+) (133.3320 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 5 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 6 (+) (166.6650 millimetres)
1) -1.0 2) -1.0 3) -1.0 4) -1.0
5) -1.0
Target 6 (-)
1) -1.0 2) -1.0 3) -1.0 4) -1.0
5) -1.0

Target 7 (+) (199.9980 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 7 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 8 (+) (233.3310 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 8 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 9 (+) (266.6640 millimetres)
1) -1.0 2) -1.0 3) 0.0 4) 0.0
5) 0.0
Target 9 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 10 (+) (299.9970 millimetres)
1) -1.0 2) -1.0 3) -1.0 4) -1.0
5) -1.0
Target 10 (-)
1) -1.0 2) -1.0 3) -1.0 4) -1.0
5) -1.0

Target 11 (+) (333.3300 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 11 (-)
1) 1.0 2) 0.0 3) 0.0 4) 1.0
5) 1.0

Target 12 (+) (366.6630 millimetres)
1) -1.0 2) -1.0 3) -1.0 4) -1.0
5) -1.0
Target 12 (-)
1) -1.0 2) -1.0 3) -1.0 4) -1.0
5) -1.0

Target 13 (+) (399.9960 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 13 (-)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0

Target 14 (+) (433.3290 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 14 (-)
1) 0.0 2) 0.0 3) 1.0 4) 1.0
5) 1.0

Target 15 (+) (466.6620 millimetres)
1) 0.0 2) 0.0 3) 0.0 4) 0.0
5) 0.0
Target 15 (-)
1) 0.0 2) 0.0 3) 0.0 4) 1.0
5) 1.0

Target 16 (+) (499.9950 millimetres)
1) 1.0 2) 0.0 3) 0.0 4) 1.0
5) 1.0
Target 16 (-)
1) 1.0 2) 1.0 3) 1.0 4) 1.0
5) 1.0

ACE MANUFACTURING SYSTEMS LTD

INSPECTION REPORT-BASE BUILDING. 2 GUIDEWAYS

AMS *In Pursuit of Excellence*

MACHINE NUMBER: MIL- 805 **DATE:** 02/04/19

I. MACHINE BASE LEVELING: Least count of the Instrument: 1 div = 0.020mm / meter



SL NO	DESCRIPTION	RECOMMENDED (mm)	ACTUAL(mm)		
1	Leveling - Length wise (Longitudinal)	1 div / meter	1 div.		
2	Leveling - Height variation between loc/non-loc guide ways	1 div / meter	¼ div.		
3	Leveling - Individual (Transverse)	3 div / meter	2½ div.		
4	Straightness of locating guide way	± 0.005	0.001 mm		
5	Parallelism of Non locating guide way w.r.t.locating guide way	±0.005	0.002 mm		
6	Ball screw Run out at Motor end	±0.010	0.008 mm		
7	Ball screw Run out at Brake end	±0.010	0.006 mm		
8	Ball screw alignment w.r.t. Top guide way	±0.020	0.010 mm		
9	Ball screw alignment w.r.t. locating Side guide way	±0.020	0.010 mm		
10	Ball screw Stretching	0.025 (±0.002 /meter)	0.025 mm		
			M.E	CEN	B.E
11	Ball screw Torque	0.6 to 1.8 N-m	1.25	1.25	1.25 N/m
12	Slide & Jib Torque (Not applicable for LM guide way)	Ball Screw Torque + 0.5 to 1.0	–	–	–
13	Slide, Jib & Single Keeper plate Torque (Not applicable for LM guide way)	Ball Screw Torque + 0.5 to 1.0	–	–	–
14	Slide, Jib & Both Keeper plate Torque (Not applicable for LM guide way)	Ball Screw Torque + 0.5 to 1.0	–	–	–
15	Final slide Torque – box guide way	2.5 to 3 N-m	–	–	–
16	Final slide Torque – L M rail	1.6 to 2.5 N-m	1.75	1.75	1.75 N/m
17	Variation in torque for final slide	10%			
18	Remarks if any :	–	–	–	–

SIGN & DATE				1...10	F-QA-IPR-BBA-03-R0
	PREPARED	CHECKED	APPROVED	PAGE NUMBER	FORMAT NUMBER

ACE MANUFACTURING SYSTEMS LTD
INSPECTION REPORT-BASE BUILDING. 2 GUIDEWAYS

AMS
In Pursuit of Excellence

MACHINE NUMBER: MH-805 DATE: 02/04/13

SL NO	Check Points	Remark
1	Ensure all leveling screws & locknuts are fixed to the base.	✓
2	Ensure guide way butting face blue matching is minimum 70%	✓
3	Ensure locating & non locating guide way are fitted at respective position (L M m/c only)	✓
4	Ensure position of LM block ground surface butted to slide butting face.	✓
5	Ensure required height blocks are fitted to the base as per Work Order / Planning chart.	✓
6	Ensure plugs are fitted for L M guide way	✓

DATE: 03/04/13

II. SADDLE LEVEL READING: Least count of the Instrument: 1 div = 0.020mm / meter



Remarks if any :

—

SIGN & DATE					
	PREPARED	CHECKED	APPROVED	PAGE NUMBER	FORMAT NUMBER
				2...10	F-QA-IPR-BBA-03-R0

ACE MANUFACTURING SYSTEMS LTD

INSPECTION REPORT-BASE BUILDING. 2 GUIDEWAYS

AMS
In Pursuit of Excellence

MACHINE NUMBER: 411-805 **DATE:** 03/04/19

SL NO	DESCRIPTION	RECOMMENDED (mm)	ACTUAL(mm)		
1	Leveling - Length wise (Longitudinal)	2 div / meter	2 div.		
2	Leveling - Height variation between loc/non-loc guide ways	1 div / meter	½ div.		
3	Leveling - Individual (Transverse)	3 div / meter	2 div.		
4	Straightness of locating guide way	± 0.005	0.003 mm		
5	Parallelism of Non locating guide way w.r.t.locating guide way	±0.005	0.003 mm		
6	Ball screw Run out at Motor end	±0.010	0.008 mm		
7	Ball screw Run out at Brake end	±0.010	0.006 mm		
8	Ball screw alignment w.r.t. Top guide way	±0.020	0.010 mm		
9	Ball screw alignment w.r.t. locating Side guide way	±0.020	0.010 mm		
10	Ball screw Stretching	0.025 (±0.002 /meter)	0.025 mm		
			M.E	CEN	B.E
11	Ball screw Torque	0.6 to 1.8 N-m	1.5	1.5	1.5 N/m
12	Slide & Jib Torque (Not applicable for LM guide way)	Ball Screw Torque + 0.5 to 1.0	–	–	–
13	Slide, Jib & Single Keeper plate Torque (Not applicable for LM guide way)	Ball Screw Torque + 0.5 to 1.0	–	–	–
14	Slide, Jib & Both Keeper plate Torque (Not applicable for LM guide way)	Ball Screw Torque + 0.5 to 1.0	–	–	–
15	Final slide Torque – box guide way	2.5 to 3 N-m	–	–	–
16	Final slide Torque – L M rail	1.6 to 2.5 N-m	2.0	2.0	2.0 N/m
17	Variation in torque for final slide	10%			

Remarks if any :

–

ACE MANUFACTURING SYSTEMS LTD
INSPECTION REPORT-BASE BUILDING. 2 GUIDEWAYS

AMS
In Pursuit of Excellence

MACHINE NUMBER: MH-805 DATE: 08/04/19

SL NO	Check Points	Remark
1	Ensure oil connecting holes are made clear by passing air & kerosene	✓
2	Ensure guide way butting face & saddle bottom blue matching is minimum 80%	✓
3	Ensure tightness of Eccentric pin locknuts. ((H G m/c only)	NA
4	Ensure proper taper matching of jib. ((H G m/c only)	NA
5	Ensure locating & non locating guide way are fitted at respective position (L M m/c only)	✓
6	Ensure position of LM block ground surface butted to slide butting face. (L M m/c only)	✓
7	Ensure Equal gap between ball nut & nut housing bore.	✓
8	Ensure Nut housing alignment is with in 0.010 mm/meter	✓
9	Ensure White Prussian matching between nut housing & ball nut butting face is80%	✓
10	Ensure bearing housing Dowelling and grub locking.	✓
11	Ensure Ball screw lock nut grub locking with lock tite.	✓
12	Ensure guide way wipers are fixed. (H G m/c only)	NA
13	Ensure Nylon stoppers are fixed as per specification.	✓
14	ensure plugs are fitted for lm guide way & grub screws are fixed to saddle mounting holes	✓

DATE: 09/04/19

III. COLUMN READING: **Least count of the Instrument: 1 div = 0.020mm / meter**



Remarks if any :

SIGN & DATE					
	PREPARED	CHECKED	APPROVED	PAGE NUMBER	FORMAT NUMBER
				4...10	F-QA-IPR-BBA-03-R0

ACE MANUFACTURING SYSTEMS LTD

INSPECTION REPORT-BASE BUILDING. 2 GUIDEWAYS

AMS — In Pursuit of Excellence

MACHINE NUMBER: VMC-805 **DATE:** 09/04/19

SL NO	DESCRIPTION	RECOMMENDED (mm)	ACTUAL(mm)		
1	Leveling - Length wise (Longitudinal)	1 div / meter	½ div		
2	Leveling - Height variation between loc/non-loc guide ways	1 div / meter	0 div		
3	Leveling - Individual (Transverse)	3 div / meter	3 div.		
4	Straightness of locating guide way	± 0.005	0.002 mm		
5	Parallelism of Non locating guide way w.r.t.locating guide way	±0.005	0.005 mm		
6	Ball screw Run out at Motor end	±0.010	0.008 mm		
7	Ball screw Run out at Brake end	±0.010	0.006 mm		
8	Ball screw alignment w.r.t. Top guide way	±0.020	0.010 mm		
9	Ball screw alignment w.r.t. locating Side guide way	±0.020	0.010 mm		
10	Ball screw Stretching	0.025 (±0.002 /meter)	0.005 mm		
11	Mandrel radial run out	±0.010	0.008 mm		
12	Mandrel reading at Top (parallelism wrt.head stock movement)	±0.010	0.006 mm		
13	Mandrel reading at side (parallelism wrt.head stock movement)	±0.010	0.004 mm		
			M.E	CEN	B.E
14	Ball screw Torque	0.6 to 1.8 N-m	1.25	1.25	1.25 N/m
15	Slide & Jib Torque (Not applicable for LM guide way)	Ball Screw Torque + 0.5 to 1.0	—	—	—
16	Slide, Jib & Single Keeper plate Torque (Not applicable for LM guide way)	Ball Screw Torque + 0.5 to 1.0	—	—	—
17	Slide, Jib & Both Keeper plate Torque (Not applicable for LM guide way)	Ball Screw Torque + 0.5 to 1.0	—	—	—
18	Final slide Torque – box guide way	2.5 to 3 N-m	—	—	—
19	Final slide Torque – L M rail	1.6 to 2.5 N-m	1.75	1.75	1.75 N/m
20	Variation in torque for final slide	10%			

Remarks if any :

—

SIGN & DATE				5...10	F-QA-IPR-BBA-03-R0
	PREPARED	CHECKED	APPROVED	PAGE NUMBER	FORMAT NUMBER

MACHINE NUMBER: MH-805 DATE: 09/04/19

SL NO	Check Points	Remark
1	Ensure oil connecting holes are made clear by passing air & kerosene.	✓
2	Ensure guide way butting face, head stock bottom face,& column bottom face blue matching is minimum 80%	✓
3	Ensure tightness of Eccentric pin locknuts. ((H G m/c only)	NA
4	Ensure proper matching of jib taper. ((H G m/c only)	NA
5	Ensure locating & non locating guide way are fitted at respective position (L M m/c only)	✓
6	Ensure position of LM block ground surface butted to slide butting face. (L M m/c only)	✓
7	Ensure Equal gap between ball nut & nut housing bore.	✓
8	Ensure nut housing alignment is with in 0.010 mm	✓
9	Ensure White Prussian matching between nut housing & ball nut butting face is 80 %	✓
10	Ensure spindle cartridge butting face blue matching is 80%	✓
11	Ensure head stock is fixed as per requirement (ID, DD, and DD CTS).	✓
12	Ensure bearing housing Dowelling and grub locking.	✓
13	Ensure Ball screw lock nut grub locking with locktite.	✓
14	Ensure guide way wipers are fixed. (H G m/c only)	NA
15	Ensure Nylon stoppers are fixed as per specification.	✓
16	Ensure machine lifting tackles are fitted.	✓
17	Ensure plugs are fitted for lm guide way & grub screws are fixed to head stock mounting holes	✓

MACHINE NUMBER: DATE:

IV. SIDE ARM ALINGMENT READING: (Turret Type ATC only)

SL NO	DESCRIPTION	Recommended (mm)	ACTUAL (mm)
1	Shaft reading at Top (longitudinal)	±0.050	
2	Shaft reading at side (transverse)	±0.030	
3	Square ness of locating side	±0.010	
4	Distance between Z axis guide way top surface & side arm bore centre	REFER AS PER DRAWING NO	NA
5	Distance between sidearm front butting face on column & side arm bore centre	REFER AS PER DRAWING NO	

Remarks if any : —

ACE MANUFACTURING SYSTEMS LTD

INSPECTION REPORT-BASE BUILDING. 2 GUIDEWAYS

AMS — In Pursuit of Excellence

MACHINE NUMBER: M1~~0~~805 **DATE:** 10/04/13

RECOMMENDED TOLERANCE AS PER DS – DSN – TC – PROD – 01 – R0

V. LEVELLING OF MACHINE: **L.C of Instrument: 1 div = 0.020mm / m**

Along X-axis			Along Y-axis		
Motor End	Middle	Brake End	Motor End	Middle	Brake End
3/4 →	← 0 →	← 0	↑ 1/4	↑ 1/4	↑ 1/4
3/4 →	← 0 →	← 1/4	↕ 0	↕ 0	↕ 0
3/4 →	← 0 →	← 1/4	↓ 1/2	↓ 1/2	↓ 1/2

VI. TABLE TOP READING ALONG X- AXIS:

0	-2	-4	0
0	-2	-4	0
0	-1	-2	0
0	-1	-2	+2

VII. TABLE TOP READING ALONG Y- AXIS:

0	0	0	0
-6	-7	-6	-7
-8	-7	-7	-7
-4	-5	-4	-3

ACE MANUFACTURING SYSTEMS LTD
INSPECTION REPORT-BASE BUILDING. 2 GUIDEWAYS

AMS
In Pursuit of Excellence

MACHINE NUMBER: 2111-805 DATE: 11/04/13

VIII. PARALLELISM OF REFERENCE T-SLOT TO X-AXIS MOVEMENT AT FRONT & REAR SURFACE:

0	-6	-3
0	+4	+4

SL NO	Check Points	Remark
1	Ensure oil connecting holes are made clear by passing air	✓
2	Ensure table bottom face blue matching IS minimum 70%	✓
3	Ensure tightness of Eccentric pin locknuts. ((H G m/c only)	NA
4	Ensure proper matching of jib taper. ((H G m/c only)	NA
5	Ensure position of LM block ground surface butted to slide butting face.	✓
6	Ensure Equal gap between ball nut & nut housing bore.	✓
7	Ensure nut housing parallelism is with in 0.010 mm	✓
8	Ensure Blue matching between nut housing & ball nut butting face is 70%	✓
9	Ensure Table Tenon slot size as per specification	✓

IX. SQUARENESS OF Y –AXIS MOVEMENT WITH RESPECT TO X – AXIS MOVEMENT:



Remarks if any :

SIGN & DATE					
	PREPARED	CHECKED	APPROVED	PAGE NUMBER	FORMAT NUMBER
				8...10	F-QA-IPR-BBA-03-R0

ACE MANUFACTURING SYSTEMS LTD

INSPECTION REPORT-BASE BUILDING. 2 GUIDEWAYS

AMS *In Pursuit of Excellence*

MACHINE NUMBER: M11-805 **DATE:** 11/04/15

X. COLUMN READING (INITIAL):

XZ PLANE(SIDE)

500	-30
450	
400	
350	
300	
250	-15
200	
150	
100	
50	
0	0

YZ PLANE (FRONT)

500	-19
450	
400	
350	
300	
250	-6.
200	
150	
100	
50	
0	0

COLUMN READING - FINAL:

XZ PLANE(SIDE)

500	
450	
400	
350	
300	
250	
200	
150	
100	
50	
0	

YZ PLANE (FRONT)

500	
450	
400	
350	
300	
250	
200	
150	
100	
50	
0	

ACE MANUFACTURING SYSTEMS LTD
INSPECTION REPORT-BASE BUILDING. 2 GUIDEWAYS

AMS
In Pursuit of Excellence

MACHINE NUMBER: M11-805 DATE: 11/04/19

XI. COLUMN ALINGMENT READING WITH RESPECT TO X-AXIS MOVEMENT:
PERMISSIBLE VALUE = 0.30MM/METRE



0										±0.1mm
0	100	200	300	400	500	600	700	800	900	1000

Remarks if any :

SIGN & DATE					
	PREPARED	CHECKED	APPROVED	PAGE NUMBER	FORMAT NUMBER
				10...10	F-QA-IPR-BBA-03-R0

ACE MANUFACTURING SYSTEMS LTD

LUBRICATION ASSEMBLY - INSPECTION REPORT- BBA

AMS *In Pursuit of Excellence*

MACHINE NUMBER : M-11-805

I. Lubrication metering cartridge specification (cc of oil / shot) as per DS-PDN-MEC-LUB-01 :

Sl. No.	Axis	Ball screw	Box guideway top / LM block	Box guideway side	Jib	Keeper plate
1	X -Axis	0.25cc	0.1cc	—	—	—
2	Y -Axis	0.25cc	0.1cc	—	—	—
3	Z-Axis	0.25cc	0.1cc	—	—	—

Sl. No.	Check points:	Remark
1	Verify that metering cartridge are fixed as per DS-PDN-MEC-LUB-01.	✓
2	Ensure X,Y & Z guideways and ball screw are lubricating properly	✓
3	Ensure lubrication pressure set to 15 Bar.	✓
4	Ensure there is no leakage of oil-from joints, cartridges & manifolds etc.	✓
5	Ensure that the lubrication hoses do not rub or foul with the stationary / moving parts during axis movement.	✓
6	Ensure that the lubrication hoses of appropriate length (as per DS-PDN-MEC-LUB-01) are used and properly clamped and routed.	✓

II Telescopic cover Assembly:

	Sl No	Axis	Extension block Parallelism w.r.t. axis guideway		Extn. Block Length Variation -	DRAWING NUMBER
			Top - Recommended 0.020 mm	Side- Recommended 0.030 mm	Recommended 0.050 mm	(S10 -)
	1	X - Motor End	+0.02"	+0.03"	+0.05"	—
	2	X - Brake End	+0.02"	+0.03"	+0.05"	—
	3	Y - Motor End	+0.02"	+0.03"	—	—
	4	Y - Brake End	+0.02"	+0.03"	+0.05"	—
	5	Z - Brake End	+0.02"	+0.03"	+0.05"	—

III. Saddle cover alignment w.r.t. Y axis movement (If applicable) :

	Sl NO	Top - Recommended 0.050 mm	Side - Recommended 0.050 mm	
	1	—	—	—

IV. Check Points :

Sl NO	Check points:	Remark
1	Check telescopic cover sliding smoothly	✓
2	Ensure telescopic cover screws are tightened in box close condition	✓

Date: 16/04/24	PREPARED	CHECKED	APPROVED

ACE MANUFACTURING SYSTEMS LTD

LUBRICATION ASSEMBLY - INSPECTION REPORT- BBA

AMS — In Pursuit of Excellence

MACHINE NUMBER : M-11-805

V. Axis Motor Assembly :

Motor mounting bracket Concentricity & Face out:

Sl No	Axis	Face out -Recommended 0.030 mm	Concentricity Recommended 0.060 mm
1	X- Axis	+0.03"	+0.06"
2	Y- Axis	+0.03"	+0.06"
3	Z- Axis	+0.03"	+0.06"

Sl NO	Check points:	Remark
1	Ensure motor shaft and coupling bore are free from oil / grease before fitting of coupling	✓
2	Ensure Axis Motor & Motor mounting bracket are fitted as per specification.	✓
3	Ensure that slot on Steel Bellows, Clamping ring & Bush are in line.	✓
4	Ensure tightness of coupling is set to torque value of 17 N-m (M6 screw), 35 N-m (M8 screw).	✓

VI. Counter balance Assembly (If applicable)

Sl NO	Check points:	Remark
1	Ensure Smooth movement of Z- Axis without fouling of dead weight. (MCV 500 / MCV 600 only)	—
2	Ensure the parallelism of counter balance cylinder piston is within 0.050 mm in both XZ & YZ planes with respect to Z Axis movement.	—
3	Ensure variation in the vertical axis motor current is within 20% during upward and downward movement of slide.	—
4	Ensure dowelling of counterbalance bracket.	—

REMARK IF ANY:

16/04/12			
Date:	PREPARED	CHECKED	APPROVED